

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-21276-00-00  
Spot: N2S2NWNE Sec/Twnshp/Rge: 4-29S-12W  
810 feet from N Section Line, 1980 feet from E Section Line  
Lease Name: ONSTOT Well #: 2  
County: PRATT Total Vertical Depth: 4641 feet

Operator License No.: 30705  
Op Name: YOUNGER ENERGY COMPANY  
Address: 453 S. WEBB RD., STE 100  
WICHITA, KS 67207

PROD Size: 5.5 feet: 4402 WITH 225 SX CMT  
SURF Size: 8.625 feet: 410 WITH 300 SX CMT

#150<sup>83</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/02/2005 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Revd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND BACK TO 4160' & 5 SX CMT. PLUG AT 700' WITH 10 SX GEL & 50 SX CMT. PLUG AT 440' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/02/2005 10:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4160' & 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 700' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 440' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4256	4562		
4216	4219		

RECEIVED  
JUN - 6 2005  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2400' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

*Stephen J. [Signature]*  
(TECHNICIAN)

INVOICED  
DATE 6-7-05  
INV. NO. 2005061682

Form 2/3  
*[Signature]*