

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-21284-00-00  
Spot: SWNE Sec/Twnshp/Rge: 4-29S-12W  
1980 feet from N Section Line, 2060 feet from E Section Line  
Lease Name: ONSTOT Well #: 3  
County: PRATT Total Vertical Depth: 4600 feet

Operator License No.: 30705  
Op Name: YOUNGER ENERGY COMPANY  
Address: 453 S. WEBB RD., STE 100  
WICHITA, KS 67207

PROD Size: 5.5 feet: 4599 WITH 200 SX CMT  
SURF Size: 8.625 feet: 386 WITH 300 SX CMT # 149<sup>50</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/26/2005 10:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Revd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND BACK TO 4002' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH BAILER. PLUG AT 700' WITH 10 SX GEL & 50 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/26/2005 11:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4002' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 700' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4258	4265		
4084	4090		

RECEIVED  
JUN - 6 2005  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2240' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

*Stephen J. Pfeifer*  
(TECHNICIAN)

INVOICED  
DATE 6.7.05  
INV. NO. 2005061682

Form CS-21