

4-110103

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-051-25,045 -00-00  
190'N. & 60'W.  
SW SE NW /4 SEC. 06, 11 S, 20 W  
3160 feet from S section line  
3690 feet from E section line

Operator license# 5259  
Operator: Mai Oil Operations, Inc.  
Address: P.O. Box 33  
Russell, Kansas 67665

7/22

Lease: Richards Well # 7  
County: Ellis 120, 12  
Well total depth 3696 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 260 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: VonFeldt Drilling License# 9431

Address: P.O. Box 611 - Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 22 Month: July Year: 2000

Plugging proposal received from: Craig Davidson

Company: VonFeldt Drilling Phone: 785-483-1684

Were: Plug according to Rules & Regulations set forth by the Kansas Corporation Commission.

Plugging Proposal Received by: Roger Moses

Plugging operations attended by agent? All , Part , None

Completed: Hour: 12:45 P.M., Day: 22, Month: July, Year: 2000

Actual plugging report: Set 8 5/8" S.P. at 260' w/185 sxs cement.

1<sup>st</sup>. Plug at 3680' w/25 sxs - Arbuckle.

2<sup>nd</sup>. Plug at 1540' w/25 sxs - Anhydrite 1519' - 1565'.

3<sup>rd</sup>. Plug at 760' w/100 sxs - Dakota 466' - 766'.

4<sup>th</sup>. Plug at 310' w/40 sxs - Surface pipe at 260'.

5<sup>th</sup>. Plug at 40' w/10 sxs and 8 5/8" wiper plug. 15 sxs in rathole.

Total 215 sxs 60/40 pozmix - 6% gel and 1/4# flocele per sack.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 4 2000  
8/4/2000  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Allied Cementing

Condition of casing(in hole): GOOD  BAD  Anhy.plug: YES  NO

Bottom plug(in place): YES  CALC  NO  Dakota plug: YES  NO

Plugged through TUBING , CASING  Elevation: 2050 GL

I did  / did not  observe the plugging.

INVOICED  
DATE 8/10/00  
INV. NO. 1060346

Roger A. Moses  
(agent)

Form CP-2/3  
MB