

8-4

4-080220

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, ROOM #2078
WICHITA, KANSAS 67202-3802

RECEIVED
KANSAS OIL & GAS
FRT SEP 24 10 2:07
9/24/1997

NEE 5/13/05

API number: 15- 051-24,971-0000

NE
NW NE /4 SEC: 06- 11- 20 W
4950 Feet from S (N/S) Line
1580 Feet from E (E/W) Line

Operator License# 5259

LEASE: Richards WELL # 6

Operator: Mai Oil Operations, Inc.

County: RUSSELL 120.58

Address: Box 33
Russell, Kansas
67665

Well total Dept 3710 feet
Conductor Pipe inch @ feet
Surface pipe 8 5/8 inch @ 224 feet

Aband. Oil Wel Gas Well Input Well SWD: D & A: X

Pluggin contractor: Shields Drilling License#: 5134

Address: Russell, Kansas

Company to plug at: Hour: ?? Day: Month: Year:

Plugging proposal received from: Burton Berry

Company: Shields Drilling Phone:

Were: Spot plugs through drill pipe w/ heavy mud between all plugs

1 st plug 1570 feet with 25 sacks Rat hole: 15 sacks
2nd plug @ 780 feet with 100 sacks Mouse hole: 10 sacks
3rd plug @ 275 feet with 40 sacks Wiper plug @ 40 foot
4th plug 40 feet with 10 sacks
5th plug feet with sacks

Plugging proposal recived by: Bruce
Pluggings operations attended by agent? All [], Part [], None [X]

Completed Hour: 04:45 pm Day: 4 Month: August Year: 1997

Actual plugging report: Hole reported plugged as above.
Order 225 sx 60/40 Posmix w/ 6% gel and 10 sx celloflake or flowcel.

Remarks: Elevation: 2082 GL, Anhydrite top: 1554 feet Anhy. plug: y

Dakota plug: y Bottom plug in place y

Plugged through drill pipe

Arbuckle top Cemented by: Allied Cementing

I did [] did NOT [X] observe the plugging.

Bruce Basye
Bruce Basye
(agent)

ND

INVOICED

DATE 9-24-97
INV. NO. 49098