

4-041592

7-22

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-051-05321-00-01

NE NE SE /4 SEC. 06, 11 S, 20 W
2310 feet from S section line
330 feet from E section line

Operator license# 5259

Lease Richards well # V-1

Operator: Mai Oil Operations, Inc.

County Ellis

Address: P.O. Box 33
Russell, Kansas 67665

Well total depth 810 feet ^{35'}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 200 feet

Aband. oil well , Gas well , Input well , SWD , D & A OWWO

Plugging contractor: Halliburton Cementing License#

Address: Hays, Kansas 67601

Company to plug at: Hour: 11:00A.M Day: 22 Month: July Year: 94

Plugging proposal received from: Allen Bangart

Company: Mai Oil Operations, Inc. Phone:

Were: OWWO - Out of the hole at 800+.
Ordered 100 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 300# hulls.

Plugging Proposal Received by: Dennis Hamel - Herb Deines
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 12:45P.M., Day: 22, Month: July, Year: 94

Actual plugging report: Ran in hole with tubing to 750'. Spot 25 sxs. cement with 100# hulls. Pulled tubing to 250' and circulate to surface with 250 sxs. with 200# hulls. Pulled tubing and squeezed casing with 5 sxs. cement to 500# P.S.I.

RECEIVED
STATE CORPORATION COMMISSION
JUL 28 1994
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Check cement top - O.K. - Dennis Hamel
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: GL

I did X] did not [] observe the plugging.

Dennis L. Hamel

DATE 7-28-94

(agent)

INV. NO. 40919

Form CP-2/3

7-22