

3021268

15.00 (01941.00.00)

TO:

API NUMBER 15- CONTROL #970154

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
WICHITA STATE OFFICE BLDG., 130 S. MARKET
WICHITA, KANSAS 67202

SWSE SW, SEC. 10, T 26 S, R 18 E

110 FEET FROM SOUTH SECTION LINE

3465 FEET FROM EAST SECTION LINE

LEASE NAME A.M. PIPE CO. WELL # OW-1

COUNTY ALLEN

TECHNICIAN'S PLUGGING REPORT

WELL TOTAL DEPTH APPROX. 800 FEET

OPERATOR LICENSE # 101

CONDUCTOR PIPE: SIZE FEET

OPERATOR: STATE OF KANSAS Fee Fund

SURFACE CASING: SIZE 8 FEET 8

NAME AND FEE FUND PLUGGING

ADDRESS

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR W & W PRODUCTION CO. LICENSE NUMBER 5491

ADDRESS R.R. 2, BOX 98, CHANUTE, KS 66720

COMPANY TO PLUG AT: HOUR: 9:00AM DAY: 24 MONTH: 2 YEAR: 97

PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL

(COMPANY NAME) KANSAS CORPORATION COMMISSION (PHONE) 316-431-6946

WERE: NOTHING WAS KNOWN OF THIS WELL. 4' OF CAPPED 8" WAS REMOVED FROM THE WELL.

8' OF 8" WAS INSTALLED AS SURFACE CASING. THIS EXTENDED APPROXIMATELY 5' INTO

LIMESTONE. NO CASING WAS EVIDENT. THE PLUGGING PROPOSAL WAS TO WASH 1" TO AS DEEP

AS POSSIBLE AND CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

PLUGGING PROPOSAL RECEIVED BY C.P. TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 5:00PM DAY: 24 MONTH: 2 YEAR: 97

ACTUAL PLUGGING REPORT A 5 1/2" SWEDGE ON 1" PIPE WAS RAN TO 112'. A SOLID BRIDGE

WAS ENCOUNTERED AT THAT DEPTH. THE SWEDGE WAS REMOVED. 1" PIPE WAS WASHED TO 660'.

CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 1" AND 8" ANNULUS

AT SURFACE. THE 1" PIPE WAS REMOVED. SETTLAGE AND DISPLACEMENT WERE FILLED FROM

SURFACE. CEMENT WAS PUMPED BY CONSOLIDATED INDUSTRIAL SERVICES, INC.

REMARKS: (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED Clayton P. Titel (TECHNICIAN) FORM CP-2/3

RECEIVED KANSAS CORPORATION COMMISSION

JUN 13 2005

CONSERVATION DIVISION WICHITA, KS

bn