

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: American Warrior, Inc.

Address: P.O. Box 399

Phone: (785) 398-2270 Operator License #: 4058

Type of Well: SWD Docket #: D-24,320 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 04/13/05 (Date)

by: Mike Maier (KCC District Agent's Name)

Is ACO-1 filed? [X] Yes [] No If not, is well log attached? [] Yes [X] No

Producing Formation(s): List All (If needed attach another sheet)

Topeka Depth to Top: 3590' Bottom: 3608' T.D. 3640'
Depth to Top: Bottom: T.D.
Depth to Top: Bottom: T.D.

API Number: 15-135-20911-00-01

Lease Name: McFadden

Well Number: 1

Spot Location (QQQQ): NW - NW

660 Feet from [X] North / [] South Section Line

660 Feet from [] East / [X] West Section Line

Sec. 34 Twp. 20 S. R. 22 [] East [X] West

County: Ness

Date Well Completed: 7/22/74 original well

Plugging Commenced: 4/13/05

Plugging Completed: 04/13/05

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Row 1: Topeka, water, 3590', 3608', 8 5/8", 250', None. Row 2: 5 1/2", 4317', None.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mix 35 sacks of cement with 200# of hulls, mix 13 sacks of gel, mix 115 sacks of cement and pump down casing, maximum pressure of 1000 psi, mix & pump 15 sacks of cement down 8 5/8" Braden Head, pressure up to 400 psi and held, top off 5 1/2" casing with 15 sacks of cement. Job complete. All cement was 60/40 POZ 6% gel.

Name of Plugging Contractor: Swift Services, Inc. License #: 32382

Address: N. Highway 283, Ness City, KS 67560

Name of Party Responsible for Plugging Fees: American Warrior, Inc.

State of Kansas County, Ness, ss.

Scott Corsair (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Scott Corsair

(Address) 210 Avenue A, Bazine, KS 67516

SUBSCRIBED and SWORN TO before me this 16th day of April, 20 05



Bernice Moore Notary Public My Commission Expires: 2/7/06

RECEIVED APR 19 2005 KCC WICHITA

Bm