

STATE OF KANSAS
STATE CORPORATION
COMMISSION
130 South Market Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R. 82-3-117

API NUMBER 15-007-22768 - 00-00

LEASE NAME Bennett

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 60 days.

WELL NUMBER 1

2420 Ft. from N / S Section Line

2150 Ft. from E / W Section Line

LEASE OPERATOR Woolsey Petroleum Company

ADDRESS 125 N. Market, Suite 1000, Wichita, KS 67202

PHONE # 620-886-5606 OPERATOR'S LICENSE NO. 33168

Character of Well good

(Oil, Gas) D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5/10/2005 (date)

by Steve Durant (KCC District Agent's Name).

is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top 4282 Bottom 4330 T. D. CIBP @4450

Show depth and thickness of all water, oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				10 3/4	267	None
				4 1/2	4826	3200

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Set CIBP at 4240', dump 2 sacks portland cement with dump bailer, stretch and cut pipe at 3200, (5/12/05) pull casing, run tubing to 600', Allied pump 10sx gel to load, 50 sx cement, pull to 270', pump 60 sx, pull to 40', pump 60/40 poz, 4% jel to surface (5/13/05) top off with quick crete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address P.O. Box 187, 107 W. Fowler, Medicine Lodge, KS 67104

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Woolsey Petroleum Company

STATE OF Kansas COUNTY of Barber, ss.

John Swinford (Employee of Operator) or (Operator) of above described well, being first


duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-

described well as filled that the same are true and correct, so help me God.

(Signature) John Swinford

(Address) P.O. Box 187, Medicine Lodge, KS 67104

SUBSCRIBED AND SWORN TO before me this 9 day of June, 2005



Glenda Morrison
Notary Public

My Commission Expires: November 30, 2006

RECEIVED
JUN 10 2005
06-10-05
KCC WICHITA
BMM