

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22162-00-00

Spot: SESESW

Sec/Twnshp/Rge: 12-7S-18W

330 feet from S Section Line,

2970 feet from E Section Line

Lease Name: ZWINK/IVES

Well #: 4

County: ROOKS

Total Vertical Depth: 3563 feet

Operator License No.: 101

Op Name: KCC FEE FUND PLUG

Address: 130 S. MARKET
WICHITA, KS 67202

COND Size: 13.38 feet: 127 w/150 sxs cmt

SURF Size: 8.625 feet: 1271 w/550 sxs cmt

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 05/27/2005 9:00 AM

Plug Co. License No.: 3152

Plug Co. Name: POE SERVICING INC

Proposal Rcvd. from: ED POE

Company: KANSAS CORPORATION COMMIS Phone: (785) 623-3502

Proposed Plugging Method: Ordered out 400 sxs 60/40 pozmix - 10% gel - 900# hulls.
8 5/8" flowing 4 BPH salt water. Ran tubing to 1311' - worked thru bridges to 2240'.
Hit heavy drilling mud which was plugging tubing. Pulled back to 1200'.
Anhy. 1260' - 1300'.

Plugging Proposal Received By: HERB DEINES

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 05/27/2005 12:30 PM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Ran tubing to 1917' - hard bridge.
Allied hooked onto tubing and pumped 125 sxs 60/40 pozmix - 10% gel with 400# hulls.
Pulled tubing to 1319'. Allied pumped 220 sxs cement with 500# hulls - circulated cement.
PTOH. Allied pumped 5 sxs cement.
06/06/2005 - Topped off with 50 sxs cement.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

RECEIVED

JUN 13 2005

KCC WICHITA

Form CP-2/3

JUN 01 2005

replacement card

ANGLE OIL CO
HAYSKS

12-07S-18W
SE SE SW

4 ZWINK-IVES

site: 1/8 NW OF STOCKTON KS	city: ROOKS	API 15-163-22162
contr: RED TIGER DRLG	field: RIFFE NW	
opd: STEVEN D ANGLE		
fr date 09/20/1983	spd date 09/21/1983	drig comp 09/29/1983
	card issued 02/02/1984	last revised 02/21/2000

ELV: 1800 KB, 1795 GL SMP	
tops.....depth/ datum	
DAK SD.....795 + 1005	
B/DAK SD.....955 + 845	
ANH.....1260 + 540	
BRNVLE.....2438 - 638	
TARK LM.....2584 - 764	
TOP.....2746 - 946	
HEEB.....2959 - 1159	
TOR.....2978 - 1178	
LANS.....2998 - 1198	
BKC.....3225 - 1425	
MARM.....3265 - 1465	
ARB.....3319 - 1519	
RTD.....3563 - 1763	

COPYRIGHT 2000
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

IP status:
D & A, ARB, 09/29/1983
NO LOG
INFO RELEASED: 2/21/2000 - WAS TEMP ABD
CSG: 13-3/8" COND AT 127 / 150 SX, 8-5/8" 1271 / 550 SX
NO CORES
DST (1) 3210-3320 (LKC), / 30-30-30-30, VWB, REC 85' M
ISIP 965# FSIP 920# IFP 34# -34# FFP 56# -56#
DST (2) 3210-3322 (LKC), / 60-30-60-30, WB, REC 110'
MW ISIP 875# FSIP 818# IFP 45# -45# FFP 68# -68#
DST (3) 3300-3328 (ARB), / 60-30-60-30, FB, REC 10' SLI
OCM, 50' WM, W/TR OIL, 120' MW, W/TR OIL, 300'
WTR, W/TR OIL ISIP 1090# FSIP 1090# IFP 68# -125#
FFP 159# -227#

(over)

Not Plog - 1

ANGLE OIL CO
HAYSKS

12-07S-18W
SE SE SW

4 ZWINK-IVES

TRGT ZN: ARB (OIL), PTD 3300 (ARB), SI - EVAL FOR SWDW USE (9/30/83) - WELL NEVER COMPLETED; NO SWDW APPL GRANTED; NO FURTHER ACTIVITY RPTD; CHGD STATUS TO D & A (DATE NA)