

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-15580-00-01
Spot: SESESE Sec/Twnshp/Rge: 23-20S-12W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: BIEGE A Well #: 2
County: BARTON Total Vertical Depth: 3355 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 SOUTH MARKET STREET
WICHITA, KS 67202

CIBP Size: feet: 3300
PROD Size: 5.5 feet: 3345 125 SX CMT
SURF Size: 8.625 feet: 258 200 SX CMT

\$ 109⁰⁴

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/02/2005 8:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: JAY G SCHWEIKERT Company: LARIO OIL & GAS COMPANY Phone: (316) 265-5611

Proposed
Plugging
Method:

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/02/2005 11:00 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perforated casing at 1450' and 590'.
Tubing to 1600'.
Mixed and circulated cement with 180 sxs 60/40 pozmix - 10% gel cement with 300# hulls.
POOH. Swaged onto 5 1/2" and squeezed well with 65 sxs cement and 200# hulls.
Max. P.S.I. 350#. S.I.P. 150#.

Perfs:

Top	Bot	Thru	Comments
3341	3367		
3276	3280		
3240	3246		
3168	3170		
3150	3152		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed _____

Case Morris

(TECHNICIAN)

INVOICED
DATE 6-8-05
INV. NO. 2005061685

RECEIVED

JUN - 8 2005

KCC WICHITA

Form CP-2/3

JUN 06 2005

BRIDGEPORT & GLOBE

#2

BIEGE A

23-20-12W
SE SE SE

BARTON

County

Contr.

E 1810

Comm.

11-21-48

Comp.

12-24-48

IP

160 BOPD

PHY POT

Tops	Depth	Datum
TOP	2723	-913
HEEB	2971	-1161
BR LM	3098	-1288
LANS	3116	-1306
ARB	3314	-1534
T.D.	3355	-1545

Casing:

8" 258 SWB 5 BOPH
 5" 3345 ACID 1500
 SWB 6 BOPH

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

MAILED

5 1948