

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-21794-00-00  
Spot: NENWSE Sec/Twnshp/Rge: 21-12S-14W  
2310 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: BECKER Well #: 1  
County: RUSSELL Total Vertical Depth: 3270 feet

Operator License No.: 5146  
Op Name: RAINS & WILLIAMSON OIL CO., INC.  
Address: 220 WEST DOUGLAS, STE 200  
WICHITA, KS 67202

CIBP Size: 4.5 feet: 2920  
PROD Size: 4.5 feet: 3269 150 SX CMT  
SURF Size: 8.625 feet: 447 225 SX CMT

*28*  
*#106*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/25/2005 8:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: CLAUDE BLAKESLEY Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 663-1845

Proposed  
Plugging  
Method:

Plugging Proposal Received By: *Herb Deines*  
CASE MORRIS  
Date/Time Plugging Completed: 05/26/2005 12:30 PM

Witness Type: COMPLETE (100%)  
KCC Agent: CASE MORRIS

**Actual Plugging Report:**

Casing corroded off at 452'.  
Tubing stacked out at 466'. Could not get down.  
Ran tubing to 430' and circulated with 130 sxs 60/40 pozmix - 10% gel cement with 200# hulls.  
POOH. Tied onto 8 5/8" and pumped 20 sxs cement.  
Max. P.S.I. 600#. S.I.P. 400#.

**Perfs:**

Top	Bot	Thru	Comments
3086	3090		
2963	2966		
2940	2946		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed \_\_\_\_\_

*Case Morris*

(TECHNICIAN)

**INVOICED**

DATE 6-8-05

INV. NO. 2005061688

RECEIVED

JUN - 8 2005

KCC WICHITA

Form CP-2/3

JUN 06 2005

