

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-21603-00-00  
Spot: SWNENW Sec/Twnshp/Rge: 18-12S-14W  
4290 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: STECKEL B Well #: 2  
County: RUSSELL Total Vertical Depth: 3080 feet

Operator License No.: 5146  
Op Name: RAINS & WILLIAMSON OIL CO., INC.  
Address: 220 WEST DOUGLAS, STE 200  
WICHITA, KS 67202

COND Size: 13.38 feet: 78 85 SX CMT  
PROD Size: 4.5 feet: 3079 175 SX CMT  
SURF Size: 8.625 feet: 687 300 SX CMT

#100<sup>10</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/02/2005 8:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-7397

Proposed Plugging Method: Ordered out 185 sxs 60/40 pozmix - 10% gel - 400# hulls.  
CIBP at 2750'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/02/2005 11:30 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Topped CIBP with 4 sxs cement using a dump bailer.  
Cut casing free at 1835'.  
Pulled up to 1500' - mixed and pumped 80 sxs cement with 300# hulls.  
Pulled up to 700' - spotted 40 sxs cement with 100# hulls.  
Pulled up to 200' - circulated cement with 60 sxs cement.  
POOH. Hole full of cement.

Perfs:

Top	Bot	Thru	Comments
2966	2968		
2943	2946		
2820	2822		
2808	2810		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed \_\_\_\_\_

*Jay Pfeifer*

(TECHNICIAN)

**INVOICED**

**RECEIVED**

**JUN - 8 2005**

DATE 6-8-05

INV. NO. 20050611088

**KCC WICHITA**

**JUN 07 2005**

RAINS & WILLIAMSON OIL CO., INC.  
 435 PAGE COURT 220 W DOUGLAS #2 STECKEL "B"  
 WICHITA, KS 67202

18-12-14W  
 SW NE NW

CONTR COMPANY TOOLS CITY RUSSELL

GEOL FIELD MELLARD

E 1624 KB CM 12/28/80 CARD ISSUED 3/5/81 IP P 67 BOPD

LANS 2943-46

API 15-167-21,603

+	+
+	+
+	+

LOG	TOPS	DEPTH	DATUM
ANH	690	+ 934	
B ANH	728	+ 896	
TOP	2474	- 850	
HEEB	2728	-1104	
TOR	2747	-1123	
LANS	2780	-1156	
B KC	3034	-1410	
ARB	3070	-1446	
RTD	3080	-1456	
LTD	3080	-1456	

8 5/8" 687/300sx; 4 1/2" 3079/175sx  
 DST (1) 2814-35/30-45-60-60, 2600' GIP  
 REC 80' HOCM, 120' FROTHY OIL,  
 SIP 378-378#, FP 45-57/68-91#  
 DST (2) 2932-55/30-45-60-60, GTS/45", REC  
 60' O & GCM, 250' MCGO, SIP 206-  
 206#, FP 45-68/91-114#  
 DST (3) 2961-75/30-45-60-60, GTS/5"  
 (2ND OP), REC 60' O&GCM, 250' MCGO,  
 SIP 206-206#, FP 45-68/91-114#  
 MICT - CU, PF 12/2943-46, SWB DWN,  
 100' OIH, AC 250MCA, ON VAC, SWB  
 LD, 500' OIH, AC500, SWB 680PH, NW/6HRS  
 R & T, POP

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS