

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-20627-00-00
Spot: NWNENW Sec/Twnshp/Rge: 17-12S-17W
4950 feet from S Section Line, 3630 feet from E Section Line
Lease Name: SCHMEIDLER A Well #: 9
County: ELLIS Total Vertical Depth: 3720 feet

Operator License No.: 7383
Op Name: BOLDING, GRADY CORPORATION
Address: PO BOX 486
ELLINWOOD, KS 67526

PROD Size: 5.5 feet: 3710 125 SX CMT
SURF Size: 8.625 feet: 611 450 SX CMT

90
\$120

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/03/2005 12:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-7397

Proposed Plugging Method: Ordered out 200 sxs 60/40 pozmix - 10% gel - 300# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: PARTIAL
Date/Time Plugging Completed: 06/03/2005 2:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded off casing at 3650' and topped with 5 sxs cement using a dump bailer.
Casing parted at 970'.
Pulled up to 940' - mixed and pumped 100 sxs cement with 200# hulls.
Pulled up to 625' - spotted 30 sxs cement with 100# hulls.
Pulled up to 150' - circulated cement with 50 sxs.
POOH. Hole full of cement.

Perfs:

Top	Bot	Thru	Comments
3720			

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Jay Pfeifer
(TECHNICIAN)

100
INVOICED

DATE 6-9-05

INV. NO. 2005061695

RECEIVED

JUN - 9 2005

KCC WICHITA


Form CP-2/3

JUN 07 2005

DATE

MAO'CED

ISERN-WELLS #9 SCHMEIDLER "A" 17-12-17W
 ELLINWOOD, KANSAS APP NW NE NW
 CONTR ISERN DRLG. CTY ELLIS
 GEOL WARREN JOHNSON FIELD BEMIS-SHUTTS
 E 2170 KB CM 5/12/70 CARD ISSUED 7/2/70 IP P 10 B0 + 30 BW
 ARB 3710-20



API 15-051-20,627

SMP	TOPS	DEPTH	DATUM	
				8 5/8" 611/450SX; 5 1/2" 3710/125SX
ANHY		1382	+ 788	DST(1) 3498-3526/1', 35'M, BHP 224-149#
TOP		3141	- 971	/30", FP 15-60#
HEEB		3379	-1209	
LANS		3424	-1254	CO & DD 3720 TD SWB 6BFP 78%WTR RT&R
CH CONG		3669	-1499	
SIMP SH		3687	-1517	
ARB		3707	-1537	NO LOG
RTD		3710	-1540	
DDTD		3720	-1550	

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS