

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-22068-00-00  
Spot: NWSESE Sec/Twnshp/Rge: 17-9S-21W  
990 feet from S Section Line, 990 feet from E Section Line  
Lease Name: COOLEY Well #: 2  
County: GRAHAM Total Vertical Depth: 3750 feet

Operator License No.: 5552  
Op Name: GORE OIL COMPANY  
Address: 202 SOUTH ST. FRANCIS PO BOX 2757  
WICHITA, KS 67201

PROD Size: 5.5 feet: 3745 75 SX CMT  
SURF Size: 8.625 feet: 267 185 SX CMT

*\$121<sup>88</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/07/2005 12:00 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL COMPANY Phone: (785) 259-1928

Proposed Plugging Method: Ordered out 325 sxs Swift Multi-Density Cement - 800# hulls.  
DV Tool at 1723' w/400 sxs cwc. Anhy. 1713' - 1753'.  
Hole in casing at 3295'. Top of tubing anchor - unable to fish.  
Fluid level 600'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/07/2005 4:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2960'. Swift Services pumped 100 sxs Swift Multi-Density Cement with 400# hulls.  
Pulled tubing to 1500'. Swift Services pumped 60 sxs SMD with 300# hulls - circulated cement. PTOH. Squeezed 95 sxs SMD with 100# hulls.  
Max. P.S.I. 200#. S.I.P. 50#.  
Hole full.  
Hooked up to 8 5/8" - pumped 1/2 barrel - instant 300# - blew hole in 8 5/8" orange peel.  
DV at 1723' w/400 sxs SMD - cwc.

Perfs:

| Top  | Bot  | Thru | Comments   |
|------|------|------|------------|
| 3745 | 3749 | OH   | Completion |

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed

*Richard Williams*

(TECHNICIAN)

**INVOICED**

DATE 6-15-05

INV. NO. 2005061754

RECEIVED


JUN 15 2005

KCC WICHITA

Form CP-2/3

JUN 13 2005

AYLWARD DRILLING COMPANY  
 909 FIRST NATIONAL BANK BLDG. #2 COOLEY 17-9-21W  
 WICHITA, KS 67202 NW SE SE  
 CONTR JOHN O. FARMER, INC. CTY GRAHAM  
 GEOL KENNETH B. HAMLIN FIELD MOREL  
 ELV 2245 KB SPD 9/18/84 CARD ISSUED 12/20/84 # P 74 BO & 337 BWPD  
2240 GL ARB OH 3745-3750



| LOG  | Top   | Depth/Datum |
|------|-------|-------------|
| TOP  | ..... | 3147- 902   |
| HEEB | ..... | 3400-1155   |
| TOR  | ..... | 3424-1179   |
| LANS | ..... | 3439-1194   |
| ARB  | ..... | 3744-1499   |
| RTD  | ..... | 3749-1504   |
| LTD  | ..... | 3750-1505   |

API 15-065-22,068  
 8 5/8 " 267/185SX, 5 1/2 " 3745/75SX, DV TOOL AT 1723/400SX  
 DST (1) 3728-49 (ARB) / 30-30-60-30, 420' GIP, REC 2112' CL  
 GSY OIL, 120' HOCGM, SIP 903-923#, FP 173-759 / 817-932#,  
 BHT 108"  
 MICT - CO, (ARB OH), SWB DWN, NAT, POP, P 74 BO &  
 337 BWPD, (GR 26") 10/26/84

COPYRIGHT 1984  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS

MADE IN U.S.A.