

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01066-00-01
Spot: SENE Sec/Twnshp/Rge: 3-10S-19W
3300 feet from S Section Line, 550 feet from E Section Line
Lease Name: KORTAN Well #: 2
County: ROOKS Total Vertical Depth: 1200 feet

Operator License No.: 32169

PROD Size: 4.5 feet: 1200 163 SX CMT

Op Name: DOPITA, DON DBA MAVERICK OIL CO.

SURF Size: 8.625 feet: 171 150 SX CMT

Address: 310 E. PLAINVILLE AVE.
ZURICH, KS 67663

39⁰⁰

Well Type: SWD

UIC Docket No: D19672.0

Date/Time to Plug: 06/06/2005 9:00 AM

Plug Co. License No.: 99998

Plug Co. Name: COMPANY TOOLS

Proposal Rcvd. from: DON DOPITA

Company: MAVERICK OIL COMPANY

Phone: (785) 650-4954

Proposed
Plugging
Method:

Ordered 110 sxs 60/40 pozmix - 10% gel - 400# hulls.
PBTD 1042'. Cedar Hills SWD.

Plugging Proposal Received By: RICHARD WILLIAMS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 06/06/2005 9:30 AM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Allied tied onto 4 1/2" casing and pumped 110 sxs 60/40 pozmix - 10% gel with 400# hulls.
Max. P.S.I. 500#. S.I.P. 300#.
Hooked up to backside instant 1000#.

Top	Bot	Thru	Comments
1022	1042		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

RECEIVED

DATE 6-15-05

JUN 15 2005

REV. NO. 2005061750

KCC WICHITA

JUN 13 2005

BLACK GOLD OIL CO. #2 SWD KORTAN 'OWWO' 3-10-19W
 P.O. BOX 26 100'E,
 HAYS, KS 67601 C SE NE
 CONTR SUPERIOR WELL SERVICE CTY, ROOKS 3300FSL
 GEOL _____ FIELD ZURICH TWST SO 550FEL
 E 2148 RB CM 6/4/79 CARD ISSUED 7/21/79 IP SWDW
 CED HILL 1022-42

API NOT ASSIGNED

SMP	TOPS	DEPTH	DATUM
ANH		1503	+ 645
TOP		3098	- 950
HEEB		3312	-1164
TOR		3336	-1188
LANS		3352	-1204
BKC		3584	-1436
CONG		3625	-1477
ARB		3681	-1533
RTD		3706	-1558

OLD INFO: OPERATOR WAS DAVIS BROS
 #1 KORTON, SPD 1/18/64, SET 8" 171/
 110SX, COMPLETED AS D&A/ARB 1/30/64
 DST (1) 3319-3445/70", 250 MW, SIP 854-
 741#/20", FP 104-193#
 DST (2) 3500-90/90", 20'M, SIP 402-
 96#/20", FP 52-67#

NEW INFO: RE-ENTERED 6/4/79, WSH
 DWN TO 1200, SET 4 1/2" 1200, MICT - CO,
 PF (CED HILL) 1022-42, SWDW - INJ
 RATE SATISFACTORY

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

11/10/79
 0248
 11/10/79