

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-01555-00-00  
Spot: NENENE Sec/Twnshp/Rge: 21-9S-18W  
4950 feet from S Section Line, 330 feet from E Section Line  
Lease Name: PARADISE CREEK Well #: 205  
County: ROOKS Total Vertical Depth: 3584 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 8100 E. 22ND N. BLDG. 300  
WICHITA, KS 67226

PROD Size: 5.5 feet: 3581 150 SX CMT  
SURF Size: 8.625 feet: 1500 800 SX CMT

\$116<sup>48</sup>

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/02/2005 1:00 PM  
Plug Co. License No.: 32452 Plug Co. Name: SMOKY HILLS WELL SERVICE  
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 483-9169

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel - 400# hulls - 15 sxs gel spacer.  
CIBP at 3200'.

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/02/2005 3:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 900' and 1490'.  
TIH with tubing to 3150' - mixed and pumped 25 sxs cement followed with 15 sxs gel spacer.  
Pulled up to 1500' - circulated cement up 5 1/2" with 140 sxs cement with 100# hulls.  
POOH. Swaged onto 5 1/2" and pumped 30 sxs cement.  
S.I.P. 1000#.  
Hooked up to the annulus and pumped 50 sxs cement.  
S.I.P. 600#.

Perfs:

Top	Bot	Thru	Comments
3581	3584		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

*Jay Pfeifer*

(TECHNICIAN)  
RECEIVED

INVOICED

DATE 6-8-05

INV. NO. 2005061690

JUN - 8 2005

KCC WICHITA

Form CP-2/3

JUN 07 2005