

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23068-00-00
Spot: W2SESE Sec/Twnshp/Rge: 27-6S-21W
770 feet from S Section Line, 1020 feet from E Section Line
Lease Name: AGNES Well #: 1
County: GRAHAM Total Vertical Depth: 3868 feet

Operator License No.: 9449
Op Name: GREAT EASTERN ENERGY & DEV. CO
Address: 550 W. TEXAS STE 660
MIDLAND, TX 79702

SURF Size: 8.625 feet: 289

125⁷¹

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/04/2005 9:15 PM
Plug Co. License No.: 9292 Plug Co. Name: SCHECK, TIMOTHY DBA SCHECK OIL OPERATION
Proposal Rcvd. from: LARRY LONGHFER Company: GREAT EASTERN ENERGY & DEV. Phone: (432) 682-1178

Proposed Plugging Method: Order 225 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE
Date/Time Plugging Completed: 06/04/2005 11:15 PM KCC Agent: HERB DEINES

Actual Plugging Report:

Perfs:

1st. Plug at 3868' w/25 sxs.
2nd. Plug at 1925' w/25 sxs.
3rd. Plug at 1200' w/100 sxs.
4th. Plug at 340' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed _____

(TECHNICIAN)

INVOICED
DATE 6-8-05
INV. NO. 2005061684

RECEIVED
JUN - 8 2005
KCC WICHITA

Form CP-2/3

JUN 07 2005