

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-21591-00-01
Spot: SWNWSE Sec/Twnshp/Rge: 15-19S-20W
1650 feet from S Section Line, 2310 feet from E Section Line
Lease Name: OLIVER Well #: 1
County: RUSH Total Vertical Depth: 4444 feet

Operator License No.: 5316
Op Name: FALCON EXPLORATION, INC.
Address: 155 N. MARKET, STE. 1020
WICHITA, KS 67202

MSCC Size: feet: 681 WITH 150 SX CMT
PKR Size: feet: 3592
PROD Size: 4.5 feet: 4443 WITH 200 SX CMT
SURF Size: 8.625 feet: 308 WITH 175 SX CMT

#144 43

Well Type: SWD UIC Docket No: D27134.0 Date/Time to Plug: 05/16/2005 12:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Revd. from: LEON KUHN Company: FALCON EXPLORATION Phone: (316) 262-1378

Proposed Plugging Method: PUMP DOWN 5 1/2" CASING WITH 100# HULLS - 30 SX CMT WITH 200# HULLS MIXED IN - 33 SX GEL - 105 SX CMT. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/16/2005 1:05 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PUMPED DOWN 5 1/2" CASING WITH: 100# HULLS - 30 SX CMT WITH 200# HULLS MIXED IN - 33 SX GEL - 105 SX CMT. MAXIMUM PRESSURE 1200 PSIG. SHUT IN PRESSURE 500 PSIG. PRESSURED 8 5/8" X 5 1/2" ANNULUS TO 500 PSIG WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
3626	3720		

RECEIVED
JUN - 2 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Richard M. Lacey
(TECHNICIAN)

INVOICED
DATE 6.7.05
NO. 2005061671

Form CR-2/3