

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-20939-00-00
Spot: NESWSE Sec/Twnshp/Rge: 29-2S-27W
1055 feet from S Section Line, 1495 feet from E Section Line
Lease Name: JOHNSON Well #: 1-29
County: DECATUR Total Vertical Depth: 4150 feet

Operator License No.: 33486
Op Name: DARK HORSE OIL COMPANY LLC
Address: 34861 FOREST PARK DRIVE
ELIZABETH, CO 80107

SURF Size: 8.625 feet: 272.

134⁸⁸

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/08/2005 9:10 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: KEITH VANPELT Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER Witness Type: NONE
Date/Time Plugging Completed: 06/10/2005 8:30 AM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

Perfs:

1st. Plug at 2290' w/25 sxs.
2nd. Plug at 1450' w/100 sxs.
3rd. Plug at 325' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Ed Schumacher

(TECHNICIAN)

INVOICED

RECEIVED

DATE 6-15-05

JUN 15 2005

INV. NO. 2005061749 KCC WICHITA

Form CP-2/3

JUN 13 2005