

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-067-20412-00-00
Spot: NWNWNWSE Sec/Twnshp/Rge: 8-28S-35W
2540 feet from S Section Line, 2340 feet from E Section Line
Lease Name: PHYMELL A Well #: 2
County: GRANT Total Vertical Depth: 3115 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: 5 E. GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

CIBP Size: feet: 2870 WITH 2 SX CMT
PROD Size: 4.5 feet: 3114 WITH 225 SX CMT
SURF Size: 8.625 feet: 776 WITH 355 SX CMT

#101²⁴

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/19/2005 9:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: JOHN Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 2870' WITH 2 SX CMT. PLUG AT 1900' WITH 15 SX CMT. PLUG AT 790' WITH 50 SX CMT. PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/19/2005 12:00 PM KCC Agent: GREG PATTERSON

Actual Plugging Report:

SET CIBP @ 2870' & 2 SX CMT. TAG TOP OF FLUID AT 2785'. 1ST PLUG PUMP 14 BBL MUD TO 1900' & PUMP 15 SX CMT. DISPLACE WITH MUD. 2ND PLUG PULL OUT OF HOLE TO 790'. CIRCULATE HOLE WITH MUD & PUMP 50 SX CMT. DISPLACE WITH MUD. GOOD CIRCULATION. 3RD PLUG AT 40' LOAD HOLE WITH MUD & PUMP 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
2961	2964		
2939	2956		
2930	2934		
2910	2918		
1936			TOC

RECEIVED
JUN - 6 2005
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1322' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Gregory A. Patterson
(TECHNICIAN)

INVOICED
DATE 6.7.05
WV. NO. 20050611676

Form CP-23