

State of Kansas



15-065-20588-00-201

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 27 1972
CONSERVATION DIVISION
Wichita, Kansas

12-27-72

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Rowe of Slawson Drilling Co., Inc., has this
date requested permission to plug the following described well:

Mr. Rowe guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson,

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name: Klein Well No. B-1

Location: CSW-SE Sec. 19 Twp. 6 Rge. (E)(W) 25

County: Graham Total Depth 3855' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rowe was instructed to plug the well as follows:

330'--8 5/8" Surface casing, cement circulated with 200 Sx.

Top of Dakota section @ 1075'. (Surface casing was set on this well
approximately 2 years ago by Cimarron Drillers).

Circulate hole with heavy mud. Pull DP to 1300' and displace 110 Cu. Ft.
cement thru DP. Pull DP to 340' and displace 30 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

Conservation Division Agent