



15-179-30066-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

APR 13 1971

CONSERVATION DIVISION
Wichita, Kansas

4-13-71

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. George Sowles of A. L. Abercrombie, Inc., has this date requested permission to plug the following described well:

Mr. Sowles guarantees payment of the plugging fee.

Operator's full Name: A. L. Abercrombie, Incorporated,

Complete Address: 801 Union Center, Wichita, Kansas.

Lease Name: Vahling Well No. 3

Location: NE-NW-SW Sec. 24 Twp. 6 Rge. (E)(W) 26

County: Sheridan Total Depth 4283' Oil Well

Gas Well Input Well SWD Well X D & A Lost Hole

Mr. Sowles was instructed to plug the well as follows:

334'--8 5/8" Surface casing cement circulated. (6 3/4" Hole).
4163'--4 1/2" casing cemented on bottom with 175 Sx. Well plugged back to 3720'. Top perforations @ 3624'.

Push plug to 3550' and set well back to 3525' then set 3 S x. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 4 sacks hulls, 30 sacks gel and 160 Cu. Ft. cement, staged.

Very truly yours,

Conservation Division Agent