



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 25 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
AUG 25 1970

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Norman Cook of Abercrombie Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: A. L. Abercrombie, Inc.

Complete Address: 801 Union Center Building, Wichita, Kansas.

Lease Name: McCaughey Well No. 1

Location: NE-NE-SE Sec. 16 Twp. 7 Rge. (E)(W) 19

County: Rooks Total Depth 3420' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Cook was instructed to plug the well as follows:

225'--8 5/8" Surface casing, cement circulated with 150 Sx. (6 3/4" hole).  
Top of Dakota section @ 525'.

Circulate hole with heavy mud. Pull DP to 750' and displace 60 Sx. cement thru DP. Pull DP to 245' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent