



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Curtis of Duke Drlg. has this

date requested permission to plug the following described well:

Mr. Curtis guarantees payment of the plugging fee.

Operator's full Name: F & M Oil Co. Inc.

Complete Address: 505 Union^{ctr.}, Wichita, Ks.

Lease Name: McCormack Well No. 1

Location: SW NE NW Sec. 2 Twp. 7 Rge. (E)(W) 19

County: Rooks Total Depth 3460' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Curtis was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 50 sk cmt plug at 600' thru drill

pipe. Heavy mud to 215' set 20 sk cmt plug thru drill pipe. Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

Very truly yours, MAR 10 1977
MAR 10 1977

CONSERVATION DIVISION
Wichita, Kansas
[Signature]
Conservation Division Agent