

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 30 1967  
10/30/67  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Dobbs of E. K. Edmiston Drlg. Co. has this date requested permission to plug the following described well:

Mr. Dobbs guarantees payment of the plugging fee.

Operator's full Name: Et Al, Inc.

Complete Address: 501 Cameron Bldg., Oklahoma City, Oklahoma

Lease Name: Schneider Well No. 1

Location: C SW SE Sec. 21 Twp. 7 Rge. 19 (E)(W) X

County Rooks Total Depth 3440' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Dobbs was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720 and displace  
100 sc cement thru drill pipe. Heavy mud to 240' set cementing plug and  
displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole  
with 2 sc cement.

Very truly yours,

Leo F. Massey  
Conservation Division Agent