

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15-035-02079-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 4-18-1946 6/05

Well Operator: Marjorie O. Short dba W.D. Short Oil Co., LLC KCC License #: 6679

Address: PO Box 729 - 102 S. River Road City: Oxford

State: Kansas Zip Code: 67119 Contact Phone: (620) 455-3576

Lease: Rahn Unit #1 (E.W. Cox #2) Well #: 7 Sec. 5 Twp. 34 S. R. 6 East West

SE - NE - NW Spot Location / QQQQ County: Cowley

920 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

2100 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 10 3/4" Set at: 173' Cemented with: 200 Sacks

Production Casing Size: 6" Set at: 2845' Cemented with: 200 Sacks
4 1/2" 2919' 35 Sacks

List (ALL) Perforations and Bridgeplug Sets: _____

Elevation: 1118 (G.L. / K.B.) T.D.: 2925 PBTD: _____ Anhydrite Depth: 705'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Dump sand & fillup to 2869', dump 5 sacks cement on top of sand, pull 4 1/2" pipe, Perforate 6" @ 300' & pump cement to surface

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: William D. Short, Jr (Don)

Phone: (620) 455-3576

Address: PO Box 729 - 102 S. River Road City / State: Oxford, Kansas 67119 6/05

Plugging Contractor: Braden Well Plugging Co. KCC License #: 32475

Address: PO Box 282 - Burden, KS 67019 Phone: (620) 438-2856

Proposed Date and Hour of Plugging (if known?): Week of June 13th, 2005

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 6-14-05 Authorized Operator / Agent: William D. Short, Jr (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
06-15-05
JUN 15 2005
KCC WICHITA

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Short, W.D. and Marjorie d/b/a Short, W. D. Oil Co.
PO Box 1
Oxford, KS 67119

June 16, 2005

Re: RAHN UNIT #1 #7
API 15-035-02079-00-00
SENENW 5-34S-6E, 920 FNL 2100 FWL
COWLEY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000

Sincerely


David P. Williams
Production Supervisor