

15-163-00206-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
800 BITTING BUILDING  
WICHITA, KANSAS

WELL PLUGGING APPLICATION FORM

Lease Owner W. L. Hartman Address Box 54 - Wichita, Kansas  
(Applicant)

Lease (Farm Name) Jackson Well No. 1

Well Location NW of NW of SW Sec. 23 Twp. 7 Rge. 20 (E) or (W) W

County Books Field Name (if any) Wildcat

Was well log filed with application? Yes. If not, explain: \_\_\_\_\_

Date and hour plugging is desired to begin April 17, 1949 - 6:00 A.M.

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission, or with the approval of the following exceptions: Explain fully any exceptions desired. (Use an additional sheet if necessary) \_\_\_\_\_

Name of the person on the lease in charge of well for owner \_\_\_\_\_

W. L. Hartman Address Box 54 - Wichita, Kansas

Name of Plugging Contractor W. L. Hartman

Address Box 54 - Wichita, Kansas

Invoice covering assessment for plugging this well should be sent to:

W. L. Hartman Address Box 54 - Wichita, Kansas

and payment will be guaranteed by applicant.

**PLUGGING**  
FILE SEC 23 T 7 R 20  
BOOK PAGE 98 LINE 11

O. C. Amatt  
Applicant or Acting Agent

Date April 18, 1949

15-163-00206-00-00

JACKSON #1

Casing Record:

107' 8 5/8"

Company: W. L. Hartman

Contractor: H & H Drilg. Co.

Commenced: 4-7-49

Completed: 4-16-49

Location: NW NW SW of Sect.  
23 7S 20W, Rooks Co.,  
Kansas

Elevation: 1971 D.F. 1973 1/2 R.B.

Potential: Dry & Abandoned

\*\*\*\*\*

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Sand	0	20	Ran 107' 8-5/8 surface pipe. Cem. w/100 sx. cem., 1 sack Calcium Chloride Drilled Plug
Shale & Shells	20	107	
Shale	107	390	Jetted Pits. Trip at 1500, Bit #1. Made 1443 in 15 hrs. On bottom with Bit #2 at 10:00 a.m. Jetted Shale Pit. Jetted pits two times. Slope Test OK. SLM OK. Slope Test at 2895 OK. SLM OK Circ. for Samples at 3193- no odor. Circ. for Samples at 3251, 1 hr 14 mins. - no odor. Circ. for Samples at 3293, 1 hr Some stain. SLM OK Drill Stem Test 3293, 1 hr., 750' salt water. Circ. for Samples at 3324, 1 hr 22 mins. Circ. for Samples at 3350, 45 mins. Drill Stem Test 3364, 1 hr., Recovered 10' mud. Circ. 3418, 1 hr. 10 mins. Circ. 3430 1 hr. Circ. 3437, 1 hr. 15 mins. Circ. 3450 1 hr., 10 mins. Circ. 3460 1 hr. 7 mins. Circ. 3534, 1 hr.
Shale & Sand	390	865	
Shale & Sand	865	930	
Dolomite Sand	930	1275	
Shale	1275	1515	
Anhydrite	1515	1545	
Shale & Shells	1545	1877	
Shale & Lime	1877	2700	
Lime	2700	2960	
Lime & Shale	2960	3145	
Lime	3145	3364	
Lime & Conglomerate	3364	3474	
Conglomerate	3474	3506	
Lime	3506	3534	

TOPS: (All measurements from Robary Bushing)

(Tops Corrected to Derrick Floor)

1513	Anhydrite
2950	Topeka
3151	Heebner Shale
3167	Toronto ("Brown") Lime
3175	Lansing-Kansas City
3363	Marmaton
3428	Sooy Conglomerate
3496	Reworked Arbuckle (Conglomerate)
3504	Arbuckle Dolomite
3532	Total Depth

APR 29 1949  
 PLUGGING  
 SEC 23 T 7 R 20W  
 BOOK PAGE 93 LINE 11

I hereby certify that this is a true and correct copy of the above log, to the best of my knowledge.

*W. L. Hartman*

Subscribed and sworn to before me this \_\_\_\_\_ day of April, 1949.

My Commission expires July 14, 1951.

15-163-00206-00-00



STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
800 BITTING BUILDING  
WICHITA, KANSAS

April 25, 1949

IN REPLY PLEASE  
REFER TO THIS  
SUBJECT

Well No. <sup>1</sup>  
Lease Jackson  
Description NW 1/4 SW 1/4 23-7-20W  
County Neosho  
File No. 93-11

Mr. W. L. Hartman  
Box 54  
Wichita, Ks.

Dear Sir:

This letter is your authority to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission. When you are ready to plug this well, please contact our District Plugging Supervisor, Mr. ~~U. S. Strong~~.

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION

BY: J. P. Roberts  
J. P. ROBERTS

cc: DISTRICT PLUGGING SUPERVISOR