

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

**WELL PLUGGING APPLICATION FORM**  
(File One Copy)

API NUMBER 15-163-23,076 0500 (of this well).  
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Baird Oil Co., Inc. OPERATOR'S LICENSE NO. 5352

ADDRESS P. O. Box 428, Logan, KS 67646 PHONE # (913) 689-7456

LEASE (FARM) Jones Trust WELL NO. 1 WELL LOCATION Approx. NE NE SW COUNTY Rooks

SEC. 20 TWP. 7S RGE. 19 ~~(E) (W)~~ TOTAL DEPTH 3472' PLUG BACK TD \_\_\_\_\_

**Check One:**

OIL WELL \_\_\_ GAS WELL \_\_\_ D & A x SWD or INJ WELL \_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8" SET AT 280' CEMENTED WITH 175 SACKS

CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

PERFORATED AT \_\_\_\_\_

CONDITION OF WELL: GOOD x POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

PROPOSED METHOD OF PLUGGING Circulate heavy mud in hole. 1st plug at 3440'-25 sx. 2nd plug at 1510'-25 sx. 3rd plug at 890'-100 sx. 4th plug at 330'-40 sx. 5th plug at 40' w/wiper plug-10 sx. Rathole-15 sx. All cement 60/40 pozmix, 6% gel, 50# Flocel.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? No  
(If not explain.) Sent to operator for completion

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN at 10:45 p.m. on 01-30-90

**PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.**

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Harold Maley PHONE # (913) 674-5768

ADDRESS 216 E. McFarland, Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 1500 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

RECEIVED  
FEB 22 1990  
2/22/90  
CONSERVATION DIVISION  
Wichita, Kansas

SIGNED: Jack K. Wharton  
(Operator or Agent)

DATE: 02-12-90