

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-163-23,076 0000

LEASE NAME Jones Trust

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

2240 Ft. from S Section Line

3090 Ft. from E Section Line

SEC. 20 TWP. 7S RGE. 19 ~~WEST~~ (W)

COUNTY Rooks

Date Well Completed 01-30-90

Plugging Commenced 01-30-90

Plugging Completed 01-31-90

LEASE OPERATOR Baird Oil Co., Inc.

ADDRESS P. O. Box 428, Logan, KS 67646

PHONE# (913) 689-7456 OPERATORS LICENSE NO. 5352

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 01-31-90 (date)

by State Plugger, Hays District Office (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3472'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	280'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Circulate heavy mud in hole. 1st plug from 3440' to 3340' w/25 sx. 2nd plug from 1510' to 1410' w/25 sx. 3rd plug from 890' to 490' w/100 sx. 4th plug from 330' to 170' w/40 sx. 5th plug from 40' w/wiper plug to surface w/10 sx. Rathole-15 sx. All cement 60/40 pozmix, 6% gel, 50# Flecel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Baird Oil Co., Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton


(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct. So help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801  
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 12th day of February, 19 90

My Commission Expires: May 18, 1993  
Sharan J. Branstetter Notary Public



RECEIVED  
STATE CORPORATION COMMISSION  
2/22/90  
FEB 22 1990  
CONSERVATION DIVISION  
Wichita, Kansas