

STATE OF KANSAS
STATE CORPORATION COMMISSION

**Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas**

NORTHE

A 4x4 grid of squares, each outlined by a solid black line. The grid is further divided by dashed black lines into 16 smaller squares. The entire grid is set against a white background.

**Locate well correctly on above
Section Plat**

Name of Conservation Agent who supervised plugging of this well. Eldon Petty
Producing formation..... None Depth to top..... X Bottom X Total Depth of Well 34.56 Feet
Show depth and thickness of all water, oil and gas formations.

Name of Conservation Agent who supervised plugging of this well. Eldon Petty
Producing formation..... None Depth to top..... X Bottom..... X Total Depth of Well 3456 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface sand & Gravel	Water	0	200	8.5/8	225	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from X feet to X feet for each plug set.

Filled hole with heavy rotary mud from T.D. (3456') to 225' where a wooden plug was set and 15 sacks cement was dumped on top plug then casing was filled with mud to within 39' of top of hole and another wooden plug was set and 10 sacks cement was dumped on top plug filling casing to top and in bottom cellar and 5 more sacks cement was dumped in bottom cellar

SEP 6, 1949

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Harbar Drilling Co.
Address 1019 Central Bldg. Wichita, Kansas

STATE OF Kansas, COUNTY OF Parton, ss.
I, H. L. King, (employee of owner) or (owner or operator) of the above described, do

.....(employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____

(Address)

SUBSCRIBED AND SWEARN to before me this 1st day of

Sept 19 49
Tom Gilligan

My commission expires

9-4-50

02-5122 - 242-1035

2 42 1015

PLUGGING

15-163-00215-00-00

WALKER #1

NE^{1/4} NE^{1/4} SE^{1/4} Sec. 23-78-19W, Rooks County, Kansas

Rigging up Rotary Tools 8-17-49
Tearing out Rotary Tools 8-30-49


Run 9 Jts. 237' 8 5/8" surface pipe.
Set @ 225' and cemented with 125 sx cement.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Surface clay and sand	0	70
Shale	70	221
Lime	221	225
Shale and shells	225	360
Sand and shale	360	540
Shale and shells	540	770
Sand	770	820
Shale and sand	820	1300
Red bed	1300	1390
Anhydrite	1390	1425
Red bed	1425	1450
Shale	1450	1500
Shale and shells	1500	1855
Shale	1855	1930
Shale and shells	1930	2050
Shale and lime	2050	2730
Lime, soft	2730	2830
Shale and lime	2830	2915
Lime	2915	2980
Shale and lime	2980	3120
Lime	3120	3263
Lime and shale	3263	3295
Lime	3295	3385
Conglomerate	3385	3390
Lime	3390	3456 Total Depth

I, Don S. Packer, hereby certify that the above Log is true and correct,
to the best of my knowledge and belief.



Subscribed and sworn to before me this 1st day of September 1949.


Helen Kelly
Notary Public

My commission expires: March 22, 1952.

RECEIVED

Conservation-Div.

SEP 6 X 1949 SEP 6, 1949
STATE CORPORATION
COMMISSION
KANSAS

