

State Corporation Commission
 Conservation Division
 Wichita State Office Bldg.
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-163-21, 3920000

LEASE NAME Griebel

WELL NUMBER #1

4620 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 20 TWP. 7 RGE. 19 (E) or (W)

COUNTY Rooks

Date Well Completed August 1981

Plugging Commenced 12/28/00

Plugging Completed 12/28/00

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Baird Oil Co, Inc

ADDRESS P.O. Box 428

PHONE# (785) 689-7456 OPERATORS LICENSE NO. 5352

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/26/00 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Kansas City Depth to Top 3171 Bottom 3396 T.D. 3487

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
 KANSAS CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
<u>unconsolidated</u>	<u>sand/shale</u>	<u>surface</u>	<u>200</u>	<u>8 5/8</u>	<u>217</u>	<u>None</u>
<u>Kansas City</u>	<u>shell/limestone</u>	<u>3171</u>	<u>3396</u>	<u>4 1/2</u>	<u>3464</u>	<u>None</u>

12/21/00
 DEC 29 2000

CONSERVATION DIVISION
 WICHITA, KS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Mixed 50 SKS of 60/40 Permox 10% Gel and pumped down 8 5/8" max pressure
450'. Mixed 175 SKS of 60/40 Permox, 10% Gel with 500# of Hulls and pumped
down 4 1/2". Max pressure 750'. Well was perforated prior to plugging at 826 and 1500.

Name of Plugging Contractor Allied Cementing Co, Inc License No. 48-0727860

Address P.O. Box 31 Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Baird Oil Co, Inc

STATE OF Kansas COUNTY OF Phillips, ss.

Jim R. Baird

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jim R Baird

(Address) P.O. Box 428 Logan, KS 67646

SUBSCRIBED AND SWORN TO before me this 28th day of December, 2000

Robert B. Hartman
 Notary Public

My Commission Expires: 3/29/03

USE ONLY ONE SIDE OF EACH FORM

ROBERT B. HARTMAN
 NOTARY PUBLIC
 STATE OF KANSAS
 MY APPT. EXPIRES 3/29/03

Form CP-4
 Revised 05-88