


R

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

ROOKS County. Sec. 23 Twp. 7s Rge. 19 (W)
Location as "NE/CNW/SW" or footage from lines NW NE SE
Lease Owner PETROLEUM, INC.
Lease Name WALKER "F" Well No. 1
Office Address ROUTE 2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed 12/15 19 60
Application for plugging filed 12/15 19 60
Application for plugging approved 12/15 19 60
Plugging commenced 12/15 19 60
Plugging completed 12/15 19 60
Reason for abandonment of well or producing formation
No PRODUCIBLE FORMATIONS
If a producing well is abandoned, date of last production ---- 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ELDON PETTY
Producing formation ---- Depth to top ---- Bottom ---- Total Depth of Well 3433 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	184'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

MUDDED UP WITH HEAVY MUD TO 550' FOLLOWED BY A WOODEN PLUG. PLACED 20 SACKS OF CEMENT ON TOP OF WOODEN PLUG THROUGH DRILL PIPE, MUDDED UP WITH HEAVY MUD TO 180' FOLLOWED BY A WOODEN PLUG, PLACED 20 SACKS OF CEMENT ON TOP OF THE WOODEN PLUG THROUGH DRILL PIPE. MUDDED UP WITH HEAVY MUD TO 35' FOLLOWED BY A WOODEN PLUG AND 1/4 SACK OF HULLS. PLACED 10 SACKS OF CEMENT ON TOP OF HULLS TO BASE OF WELL CELLAR.

RECEIVED
STATE CORPORATION COMMISSION
JAN 4 1961
JAN 4 1961
CONSERVATION DIVISION
Wichita

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GARVEY DRILLING COMPANY
Address ROUTE 2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
DON SEARLE (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle
GREAT BEND, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 30TH day of DECEMBER, 19 60

My commission expires APRIL 14, 1963
Arthur J. Wile Notary Public.



WELL LOG 15-163-00815-00-00

COMPANY PETROLEUM, INCORPORATED

SEC. 23 T. 7S R. 19W

FARM WALKER "F" NO. 1


LOC. NW, NE, SE

TOTAL DEPTH 3433'

COUNTY ROOKS CO., KANSAS

COMM. December 7, 1960 COMP. December 18, 1960

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 184' w/150 sax.

ELEVATION 1910' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

30	Surface clay
240	Shale & shells
260	Sand
500	Shale & sand
625	Sand
875	Shale & shells
1100	Sand
1385	Red bed
1430	Anhydrite
1920	Shale & shells
2000	Shale & lime w/sand streaks
3140	Lime & shale
3433	Lime
3433	T. D.

RECEIVED
STATE CORPORATION COMMISSION

JAN 4 1961
JAN 4, 1961
CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS }
County of BARTON } ss.

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 WALKER "F" well

Subscribed and sworn to before me this 29th day of December 19 60

My Commission Expires: April 14, 1963

Verne A. Morris
Arthur J. Wile
NOTARY PUBLIC