

15-163-22, 810, 500-00
LEASE NAME Biery B

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER B-2
400 Ft. from S Section Line
790 Ft. from E Section Line

LEASE OPERATOR Baird Oil Co. Inc.
ADDRESS Box 428 Logan, KS 67646
PHONE# (785) 689-7456 OPERATORS LICENSE NO. 5352

SEC. 30 TWP. 07 RGE. 19 (E) or (W)
COUNTY ROCKS
Date Well Completed 11/12/85
Plugging Commenced 5-19-98
Plugging Completed 5-19-98

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)
The plugging proposal was approved on 5/1/98 (date)
by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached?
Producing Formation KC Depth to Top 3153 Bottom 3355 T.D. 3417
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Unconsolidated	sand + shale	Surface	120	8 5/8	248	None
KC + Ark	shale, limestone, dolomite	surface	3406	5 1/2	3406	None


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each section.
Pumped 240 sacks of cement (60-40 Pozmix with 10% Gel) down the casing with 5000 lbs of huffs. Pressure increased to 1000 PSI. Tied on to the 8 5/8" surface pipe and pressure up to 700 PSI. Could not pump into it.

Name of Plugging Contractor Allied License No. _____
Address P.O. Box 31 Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Baird Oil Co. Inc.
STATE OF KANSAS COUNTY OF PHILLIPS, SS.

BAIRD OIL COMPANY INC. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well, and that the same are true and correct, so help me God.

(Signature) Jean R Baird Exec VP
(Address) Box 428 Logan, KS 67646



SWORN TO before me this 21st day of MAY, 19 98
Robert B. Hartman
Notary Public

My Commission Expires: 3/29/99
USE ONLY ONE SIDE OF EACH FORM