

State Corporation Commission  
 Conservation Division  
 Wichita State Office Bldg.  
 130 S. Market, Room 2078  
 Wichita, KS 67202

PLUGGING RECORD  
 C.A.R.-82-3-117

API NUMBER 15-163-22, 5820000

LEASE NAME Cook

WELL NUMBER 4-28

2310 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 28 TWP. 7 RGE. 20 (E) or (W)

COUNTY Roark

Date Well Completed 12-31-84

Plugging Commenced 12-10-96

Plugging Completed 12-10-96

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Baird Oil Co. Inc

ADDRESS Box 428 Logan, KS 67646

PHONE# (913) 689-7456 OPERATORS LICENSE NO. 5352

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-17-96 (date)

by Dennis Hamel - Hays (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation KC Depth to Top 3459 Bottom 3480 T.D. 3480

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
-	SAND + shale	Surface	315	8 5/8	315	None
-	Shale and limestone	Surface	3459	4 1/2	3459	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set  
Perforated well at 1575 and 1000. Pumped 25 sacks cement with 2 sacks hulls followed by 10 sacks gel and then 100 sacks cement. Max pressure 900 PSI and ISIP 400 PSI. Pumped down the 8 5/8 with 1 sack of hulls and 25 sacks cement. Max pressure 500 PSI. ISIP was 100 PSI

Name of Plugging Contractor Allied Cementing Co. Inc License No. 12/13/96

Address P.O. Box 31, Russell, KS 67665


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Baird Oil Co. Inc.

STATE OF Kansas COUNTY OF Phillips, ss.

Jim R. Baird (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jim R. Baird

(Address) Box 428 Logan, KS 67646



Subscribed and sworn to before me this 11th day of DECEMBER, 19 96

Robert B. Hartman  
 Notary Public

My Commission Expires: 3/29/99  
 USE ONLY ONE SIDE OF EACH FORM