

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-22,473 0000

LEASE NAME Hansen

WELL NUMBER 1

SPOT LOCATION Apx NW SW NW

SEC. 26 TWP. 7S RGE. 20W(E) or (W)

COUNTY Rooks

Date Well Completed 9-20-84

Plugging Commenced 9-20-84

Plugging Completed 9-20-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Frontier Oil Company

ADDRESS 125 N. Market, Wichita, Ks. 67202

PHONE # (316) 263-1201 OPERATORS LICENSE NO. 5140

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dale Balthazor, Hays.

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation N/A Depth to top _____ bottom _____ T.D. 3500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Sand, Surface S	220 sx 60-40 Poz	-0-	362	8-5/8"	355.60'	-0-
Soil, Shale.	2% gel 3% cc					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged @ 3490'/25sx, 1530'/25sx, 870'/100sx & 1 sk floseal, 380'/40sx, 40'/plug 1 sk hulls & 10 sx, rathole 10sx. Cemented with 210 sx 50-50 Poz, 6% gel 3%cc. (Plugs calculated by displacement)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company License No. N/A

Address P O Box 31, Russell, Ks. 67665

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jean Angle (employee of operator) or


(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and that
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) Jean Angle

(Address) 125 N. Market, Ste 1720, Wichita

SUBSCRIBED AND SWORN TO before me this 28 day of September, 1984

Stella Sewell
Notary Public



RECEIVED
STATE CORPORATION COMMISSION
10/3/84
OCT 03 1984
CONSERVATION DIVISION
Wichita, Kansas