

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: VESS OIL CORPORATION  
Address: 8100 E. 22nd St. N., Bldg. 300, Wichita, KS 67226  
Phone: (316) 682-1537 Operator License #: 5030  
Type of Well: oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: \_\_\_\_\_ (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
lkc Depth to Top: 4174 Bottom: 4288 T.D. 4369  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - DRILLED 1941  
Lease Name: Close B  
Well Number: #1  
Spot Location (QQQQ): \_\_\_\_\_ - NW - SE - SE  
990' Feet from  North /  South Section Line  
990' Feet from  East /  West Section Line  
Sec. 30 Twp. 10S S. R. 32W  East  West  
County: Thomas  
Date Well Completed: 1/3/85  
Plugging Commenced: 5/26/05  
Plugging Completed: 5/26/05

KCC  
BANK  
6-20-05  
REBMS

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	269'	
				4-1/2	4390'	
DV Tool @ 2572'						

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged and Abandoned as follows: Connected to 8 5/8" and 4 1/2" annulus and pumped 10 sx 60/40 poz  
w/10% gel. MP - 400#; SIP - 400#. Connected to 4 1/2" casing and pumped 270 sx same cement  
with 600# hulls. MP - 600#; SIP - 500#. Approved by Darrel Dipman w/KCC.

Name of Plugging Contractor: Allied Cementing Co., Inc. License #: 99996  
Address: P.O. Box 31, Russell, KS 67665-0031  
Name of Party Responsible for Plugging Fees: Vess Oil Corporation  
State of Kansas County, Sedgwick, ss.  
Pat Canaday

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUN 17 2005  
CONSERVATION DIVISION  
WICHITA, KS

(Signature) \_\_\_\_\_  
(Address) 8100 E. 22nd Street North, Bldg. 300, Wichita, KS 67226

SUBSCRIBED and SWORN TO before me this 10th day of June  
Michelle D. Henning My Commission Expires \_\_\_\_\_  
Notary Public

MICHELLE D. HENNING  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. 11/10/05

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*Bm*

# ALLIED CEMENTING CO., INC.

19243

Federal Tax I.D.# ~~46-2700~~

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

*Close B #1*

SERVICE POINT:  
Oakley, KS

DATE <u>5-26-05</u>	SEC. <u>30</u>	TWP. <u>10</u>	RANGE <u>32w</u>	CALLED OUT <u>8:00am</u>	ON LOCATION <u>10:30am</u>	JOB START <u>11:00am</u>	JOB FINISH <u>12:45pm</u>
LEASE <u>Close</u>	WELL # <u>#1</u>	LOCATION <u>Oakley - city line +83</u>			COUNTY <u>Thomas</u>	STATE <u>KS</u>	
<input checked="" type="radio"/> OLD <input type="radio"/> NEW (Circle one)			<u>3w-1 1/2n-1 1/2w n'n</u>				

CONTRACTOR None  
 TYPE OF JOB AWP  
 HOLE SIZE \_\_\_\_\_ T.D. \_\_\_\_\_  
 CASING SIZE 4 1/2 DEPTH \_\_\_\_\_  
 TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_  
 PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_  
 MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_  
 CEMENT LEFT IN CSG. \_\_\_\_\_  
 PERFS. 4174-4288'  
 DISPLACEMENT \_\_\_\_\_

OWNER None  
 CEMENT  
 AMOUNT ORDERED 300 60/40 10%  
5el 600# hulls

COMMON	<u>168</u>	@ <u>10<sup>00</sup></u>	<u>1680<sup>00</sup></u>
POZMIX	<u>112</u>	@ <u>4<sup>70</sup></u>	<u>526<sup>40</sup></u>
GEL	<u>24</u>	@ <u>14<sup>00</sup></u>	<u>336<sup>00</sup></u>
CHLORIDE		@	
ASC		@	
		@	
<u>Hulls 60</u>		@ <u>21<sup>00</sup></u>	<u>126<sup>00</sup></u>
		@	
		@	
		@	
		@	
HANDLING	<u>332</u>	@ <u>1<sup>60</sup></u>	<u>531<sup>20</sup></u>
MILEAGE <u>.06 x mi x 5K</u>			<u>180<sup>00</sup></u>
(minimum)			
TOTAL			<u>3379<sup>60</sup></u>

**EQUIPMENT**

PUMP TRUCK CEMENTER Fuzzy  
 # 373-281 HELPER Andrew  
 BULK TRUCK  
 # 386 DRIVER Mike  
 BULK TRUCK  
 # \_\_\_\_\_ DRIVER \_\_\_\_\_

**REMARKS:**

mix & pump 10 SKs down backside  
press to 400 psi 400 shut in  
mix & pump 270 SKs down casing  
with hulls  
press to 600 shut in 500  
Job complete 12:45pm  
Thanks  
Fuzzy

CHARGE TO: Vess Oil Corp  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

To Allied Cementing Co., Inc.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE *Kenneth Rupp*

**SERVICE**

DEPTH OF JOB \_\_\_\_\_  
 PUMP TRUCK CHARGE 600<sup>00</sup>  
 EXTRA FOOTAGE @ \_\_\_\_\_  
 MILEAGE 6 @ 5<sup>00</sup> 30<sup>00</sup>  
 MANIFOLD @ \_\_\_\_\_  
 RECEIVED @ \_\_\_\_\_  
 KANSAS CORPORATION COMMISSION @ \_\_\_\_\_

JUN 17 2005  
 CONSERVATION DIVISION  
 WICHITA, KS  
 PLUG & FLOAT EQUIPMENT

TOTAL 630<sup>00</sup>  
 TAX \_\_\_\_\_  
 TOTAL CHARGE \_\_\_\_\_  
 DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

PRINTED NAME \_\_\_\_\_