


15-065-00 324-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County, Sec. 15 Twp. 7 Rge. 21 (E) W (W)
Location as "NE/CNW%SW%" or footage from lines NW NW NW
Lease Owner Trans Era Petroleum, Inc.
Lease Name Kenyon Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 5/2/53 19
Application for plugging filed 4/30/53 19
Application for plugging approved 4/30/53 19
Plugging commenced 5/1/53 19
Plugging completed 5/1/53 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3706 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	208	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

PLUGGING RECORD

Filled hole with heavy mud to 200', set first plug. Ran 15 sacks of cement through drill pipe. Filled hole with heavy mud to 40', set top plug, 1/2 sack of hulls and 10 sacks of cement used. Tied top plug to surface pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor
Address

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
Herbert R. Michaelis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *H.R. Michaelis*
Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of May, 19 53

Margie Cooper
Notary Public.

My commission expires 1-30--57.

24-7368-S 3-53-20M

PLUGGING
FILE SEC 15 T 7 R 21W
BOOK PAGE 29 LINE 10

RECEIVED
STATE CORPORATION COMMISSION
MAY 14, 1953
CONSERVATION DIVISION
Wichita, Kansas

Trans Era Petroleum, Inc.
Kenyon #1

NW NW NW 15-7-21
Graham County, Ks.

Total Depth: 3706'
Comm. 4/20/53
Comp. 5/2/53

Casing

8 5/8" Set @ 208'

Cement

130 sacks Lone Star

Formation	Depth
Surface clay	40
Shale	200
Shale-shells	918
Sand	978
Shale-shells	1280
Sand	1445
Shale	1545
Red bed-shale	1720
Anhydrite	1755
Shale-red bed	1830
Shale-shells	2080
Lime-shale	2220
Shale-shells	2470
Shale-lime	3370
Lime	3425
Lime	3565
Lime-shale	3655
Arbuckle	3673
Lime	3706'

STATE OF KANSAS)
) ss
RUSSELL COUNTY)

I hereby certify that the above information is true and correct
to the best of my knowledge.

Chris Beck

Subscribed and sworn to before me this 12th day of May, 1953.

Margie Cooper
Notary Public

My commission expires: 1-30-57.

MAY 14, 1953

RECORDED & INDEXED
MAY 14 1953
GEOLOGICAL SURVEY
KANSAS

PLUGGING
FILE SEC 15 T 7 R 21W
BOOK PAGE 99 LINE 10