

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
JUN 20 2005
KCC WICHITA
Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Apollo Energies, Inc.
Address: 10378 N. 281 Hwy
Phone: (620) 672-9001 Operator License #: 30481
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: June 3, 2005 (Date)
by: Richard Lacey (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Elgin Sand Depth to Top: 3641.5 Bottom: 3644.5 T.D. 3648.8

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-007-22741-00-00
Lease Name: Mott
Well Number: 'D' 2
Spot Location (QQQQ): 100' W - NW - SW - SE/4
990 Feet from North / South Section Line
2410 Feet from East / West Section Line
Sec. 2 Twp. 34 S. R. 13 East West
County: Barber
Date Well Completed: February 20, 1995
Plugging Commenced: June 3, 2005
Plugging Completed: June 7, 2005

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Elgin Sand	Gas/Water	0'	344'	8 5/8"	344'	0'
		0'	3648.5'	4 1/2"	3648.5'	2823'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand back to 3590', put on 4 sxs of cement on top with bailer, ripped 3018 & 2823, pull pipe to 600', spot 10 sxs of gel and 50 sxs cmt, Pull pipe to 380', spot 50 sxs cmt, pull pipe and spot 10 sxs cmt from 0 to 40'.

Name of Plugging Contractor: Quality Well Service License #: 31925
Address: 401 W. Main, Lyons, Kansas 67554
Name of Party Responsible for Plugging Fees: Apollo Energies, Inc
State of Kansas County, Pratt, ss.

Scott Alberg (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) 10378 N. 281 HWY, Pratt, Kansas 67124

KEDZIE L. RATCLIFF
Notary Public - State of Kansas
My Appt. Expires 1-10-2008

SUBSCRIBED and SWORN TO before me this 16th day of May, 2005
[Signature] My Commission Expires January 10, 2008
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten mark]