

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED

JUN 20 2005

KCC WICHITA

Form CP-4
December 2003

Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Apollo Energies, Inc.
Address: 10378 N. 281 Hwy
Phone: (620) 672-9001 Operator License #: 30481
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: June 3, 2005 (Date)
by: Richard Lacey (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Elgin Sand Depth to Top: 3670 Bottom: 3673.5 T.D. 3677

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-007-22457-00-00
Lease Name: Donovan
Well Number: 'H' #1
Spot Location (QQQQ): _____ - N/2 - N/2 - NW/4
330 Feet from North / South Section Line
1320 Feet from East / West Section Line
Sec. 11 Twp. 34 S. R. 13 East West
County: Barber
Date Well Completed: October 19, 1994
Plugging Commenced: June 2, 2005
Plugging Completed: June 3, 2005

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Elgin Sand	Gas/Water	0'	356'	8 5/8"	356'	0'
		0'	3674.5'	4 1/2"	3674.5'	2825'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand back to 3620', spot 4 sxs of cement of top with bailer. Pull 2825' of 4 1/2" casing.
Pump 300# of hulls, 10 sxs of gel, 50 sxs cmt, 10 sxs gel, 100# hulls, 8 5/8" wiper plug, 100 sxs cmt. Welded 8 5/8" collar on surface

Name of Plugging Contractor: Quality Well Service License #: 31925
Address: 401 W. Main, Lyons, Kansas 67554
Name of Party Responsible for Plugging Fees: Apollo Energies, Inc
State of Kansas County, Pratt, ss.

SCOTT ALBERG (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 10378 N. 281 HWY, Pratt, Kansas 67124

KEDZIE L. RATCLIFF
Notary Public - State of Kansas
My Appt. Expires 1-10-2008

SUBSCRIBED and SWORN TO before me this 10th day of May, 2005
Kedzie L. Ratcliff My Commission Expires: January 10, 2008
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Signature]