

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
JUN 20 2005
KCC WICHITA
Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Apollo Energies, Inc.
Address: 10378 N. 281 Hwy
Phone: (620) 672-9001 Operator License #: 30481
Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: _____ (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Simpson Sand Depth to Top: 4172 Bottom: 4178 T.D. 4178

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-185-21,011-00-00
Lease Name: Kachleman
Well Number: 1
Spot Location (QQQQ): _____ - NE - NW - SW
2300 Feet from North / South Section Line
4290 Feet from East / West Section Line
Sec. 25E Twp. 25S S. R. 13 East West
County: Stafford
Date Well Completed: January 13, 1980
Plugging Commenced: May 2, 2005
Plugging Completed: May 3, 2005

Show depth and thickness of all water, oil and gas formations.


Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Simpson Sand	oil/water	0	298'	8 5/8	298'	0
		0	4194'	4 1/2"	4194'	2420'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand back to 4120', put 4 sacks cement on top with bailer, Ripped casing at 2630, 2420' worked free pulled to 800', swedged in pumped 12 gel 50 sacks of cement, Pull pipe to 330', spot 50 sxs, 60/40 poz cement, pull pipe to 40', pumped 20 sxs, Cement fell topped off with 40 sxs cement.

Name of Plugging Contractor: Quality Well Service License #: 31925
Address: 401 W. Main, Lyons, Kansas 67554
Name of Party Responsible for Plugging Fees: Apollo Energies, Inc
State of Kansas County, Pratt, ss.

Scott Alberg
(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) _____
(Address) 10378 N. 281 HWY, Pratt, Kansas 67124

SUBSCRIBED and SWORN TO before me this 16th day of May, 2005
Kedzie L. Ratcliff My Commission Expires: January 10, 2008
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

BW