

Notice: Fill out COMPLETELY  
and return to Conservation Division  
at the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

RECEIVED

JUN 20 2005

KCC WICHITA

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

163-01555-00-00

Lease Operator: VESS OIL CORPORATION

Address: 8100 E. 22nd St. N., Bldg. 300, Wichita, KS 67226

Phone: (316) 682-1537 Operator License #: 5030

Type of Well: oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 5/25/505 (Date)

by: David Williams (KCC District Agent's Name)

Is ACO-1 filed? ☐ Yes ☒ No If not, is well log attached? ☒ Yes ☐ No

Producing Formation(s): List All (If needed attach another sheet)

Arbuckle OH Depth to Top: 3581 Bottom: 3584 T.D. 3584

Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-DRILLED 1941

Lease Name: Paradise Creek

Well Number: #205

Spot Location (QQQQ): \_\_\_\_\_ - NE - NE - NE

330' Feet from ☒ North / ☐ South Section Line

330' Feet from ☒ East / ☐ West Section Line

Sec. 21 Twp. 9S S. R. 18W ☐ East ☒ West

County: Rooks

Date Well Completed: 1/2/41

Plugging Commenced: 6/2/05

Plugging Completed: 6/2/05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	1500'	
				5-1/2	3581'	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforated at 1500' and 900'. TIH w/tubing to 3190'. Spotted 25 sx 60/40 poz w/10% gel w/15 sx gel on top.

Pulled tubing to 1550'. Circulated cement to surface with 150 sx same cement. TOH w/tbg. Tied onto 5 1/2" casing

and pumped 30 sx cement at 1000#; SIP - 1000#. Tied onto 8 5/8 and 5 1/2" annulus and pumped 50 sx cement

at 800#; SIP - 600#. Approved by Jay Pfiefer w/KCC.

Name of Plugging Contractor: Allied Cementing Co., Inc. Smokey Hills Well Service License #: 32452

Address: P.O. Box 31, Russell, KS 67665-0031

Name of Party Responsible for Plugging Fees: Vess Oil Corporation

State of Kansas County, Sedgwick, ss.

Pat Canaday (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) \_\_\_\_\_

(Address) 8100 E. 22nd Street North, Bldg. 300, Wichita, KS 67226

SUBSCRIBED and SWORN TO before me this 16th day of June, 20 05

Michelle D. Henning My Commission Expires: \_\_\_\_\_  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202  
MICHELLE D. HENNING  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appl. Exp. 7/11/15

## WELL RECORD

Company Cities Service Oil Co. Well No. 5 Farm Hilgers #A  
 Location 330' South and 330' West of NE Corner Sec. 21 T. 9 R. 18W  
 Elevation 2171 (2168 Gr.) County Rooks State Kansas  
 Drlg. Comm. October 6, 1947 Contractor R. W. Rine Drilling Company  
 Drlg. Comp. October 24, 1947 Acid 500 gals. 10-27-47  
 T. D. 3584' Initial Prod Depthograph Potential: 2325 oil, no water, 24 hours.

CASING RECORD:

8-5/8" @ 1500' with 800 sz cement  
 5-1/2" @ 3581' with 150 sz cement

FORMATION RECORD:

sand & clay	0-42
sand & shale	410
sand, shale & shells	1220
shale & shells	1485
anhydrite	1500
shale & shells	2905
lime & shale	3033
shale & lime	3291
lime & shale	3415
shale & lime	3467
lime	3569
lime & shale	3581
lime	3583
3583 Rot. TD = 3583 SLM	
lime	3584 T. D.

Top Lensing	3327'
Top Arbuckle	3581'
Penetration	3'
Total Depth	3584'

Fillup: 200' oil in 1 hr. 55 mins.  
 350' oil in 3 hours  
 1130' oil in 13 hours  
 1350' oil in 19 hours

SLOPE TESTS (ACID BOTTLE):

500'	OK
1000'	OK
1250'	OK
2500'	OK

7-7/8" rotary hole.

RECEIVED  
 JUN 20 2000  
 KCC WICHITA  
 RECEIVED  
 JUN 20 2005  
 KCC WICHITA

# ALLIED CEMENTING CO., INC.

16665

Federal Tax I.D.# ~~12-0000000~~

RECEIVED

MIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

JUN 20 2005

SERVICE POINT:

Russell

KCC WICHITA

DATE <u>6-2-05</u>	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION <u>1:00pm</u>	JOB START <u>2:00pm</u>	JOB FINISH <u>4:15pm</u>
LEASE <u>Paradise Creek</u>	WELL # <u>205</u>	LOCATION <u>Phinville 1W 1 1/4 N W 1/4</u>			COUNTY <u>Reels</u>	STATE <u>Kansas</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR Smoky Hills Well Service

TYPE OF JOB Old Hole Plug

HOLE SIZE \_\_\_\_\_ T.D.

CASING SIZE 5 1/2" DEPTH \_\_\_\_\_

TUBING SIZE 2 3/8" DEPTH \_\_\_\_\_

DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_

TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_

PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_

MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_

CEMENT LEFT IN CSG. \_\_\_\_\_

PERFS. \_\_\_\_\_

DISPLACEMENT \_\_\_\_\_

## EQUIPMENT

PUMP TRUCK	CEMENTER <u>Steve</u>
# <u>345</u>	HELPER <u>Paul</u>
BULK TRUCK	
# <u>396</u>	DRIVER <u>Fred</u>
BULK TRUCK	
# _____	DRIVER _____

## REMARKS:

Tubing @ 3200' Mix 15sks fuel &  
25 sks Cement Pull to 1500'  
Mix 140sks Cement 1 Hull & Circulated  
to top of 5 1/2" 1 2 Hulls  
Mix 30 sks down 8 1/2" shut in @ 1000psi  
Mix 50 sks down backside shut in @ 600psi

Thank You

CHARGE TO: Vess

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

To Allied Cementing Co., Inc.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE

## OWNER

## CEMENT

AMOUNT ORDERED 350 60/40 10% bel  
15 bel on side 500# Hulls

COMMON	<u>147</u>	@	<u>8.70</u>	<u>1278.90</u>
POZMIX	<u>98</u>	@	<u>4.70</u>	<u>460.60</u>
GEL	<u>32</u>	@	<u>14.00</u>	<u>448.00</u>
CHLORIDE		@		
ASC		@		

<u>50 Hulls</u>	<u>3</u>	@	<u>21.00</u>	<u>63.00</u>
		@		
		@		
		@		
		@		
		@		
		@		

HANDLING 389 @ 1.60 622.40

MILEAGE .06/sk/mile 1096.98

TOTAL 3969.88

## SERVICE

DEPTH OF JOB	
PUMP TRUCK CHARGE	<u>600</u>
EXTRA FOOTAGE	@
MILEAGE <u>4.7</u>	@ <u>5.00</u> <u>235</u>
	@
	@
	@

TOTAL 835.00

## PLUG & FLOAT EQUIPMENT

MANIFOLD	@
	@
	@
	@
	@

TOTAL \_\_\_\_\_

TAX \_\_\_\_\_

TOTAL CHARGE ~~835.00~~

DISCOUNT ~~0000~~ IF PAID IN 30 DAYS

PRINTED NAME