

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-22,424-00-00

LEASE NAME Benoit

WELL NUMBER #1

660 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 11 TWP. 7 RGE. 21W (E) or (W)

COUNTY Graham

Date Well Completed _____

Plugging Commenced 6-8-92

Plugging Completed 6-8-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS 125 N. Market, Suite 1000, Wichita, KS

PHONE#(316) 267-4375 OPERATORS LICENSE NO. 4767

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-8-92 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation L/KC Depth to Top 3382' Bottom 3651' T.D. 3662

PBTD 3658'
PC 1752'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	216'	-0-
				4 1/2"	3661'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged down 4 1/2" csg with 225 sxs 65/35 pozmix, 10% gel, & 400# hulls

Max PSI - 1000#, shut in at 800#. Plugged down 8 5/8" csg with 75 sxs

65/35 pozmix, 10% gel, & 100# hulls. Max PSI - 400#, shut in at

200#. Plugging complete at 4:30 p.m. Witnessed & approved by Carl Goodrow

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. _____

Address P.O. Box 628, Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Ritchie Exploration, Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 125 N. Market, Wichita, KS

SUBSCRIBED AND SWORN TO before me this 30th day of June, 19 92

LISA THIMMESCH
NOTARY PUBLIC
STATE OF KANSAS

[Signature]
Notary Public

APPL. EXP. 8-29-95
Commission Expires: 8-29-95

15-065-22424-00-00

GREAT GUNS

LOGGING

DIGITAL LOG

R. A. GUARD
LOG

COMPANY: RITCHIE EXPLORATION INC.
WELL: #1 BENOIT
FIELD:
COUNTY: GRAHAM

FILE NO.: H-056294

STATE: KANSAS
COUNTRY: USA

LOCATION: E/2 SE SE

SEC: 11 TWP: 7S RGE: 21W

DATE: 12/10/87

RUN NO.: 1

PERMANENT DATUM: GL
DRILLING MEASURED FROM: KB
LOG MEASURED FROM: KB
ABOVE PERMANENT DATUM: 5.0

DEPTH--DRILLER: 3662.0
DEPTH--LOGGER: 3662.0
BOTTOM LOG INTERVAL: 3659.0
TOP LOG INTERVAL: 0

CASING DEPTH--DRILLER: 216.0
CASING DEPTH--LOGGER: 216.0
CASING DIAMETER: 8.625
BIT SIZE: 7.875

UNIT NO.: 64
LOCATION: HAYS, KS
RECORDED BY: RANDY NITZ
WITNESSED BY: BOB MATHIESEN

ELEVATIONS:

KB: 2162.0
DF: .0
GL: 2157.0

SERVICES:

GR10
ENPG

RECEIVED
STATE CORPORATION COMMISSION

FEB 17 1988
CONSERVATION DIVISION
Wichita, Kansas

SOFTWARE VERSION:

401

