

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.--82-3-117

API NUMBER 15-065-22,423 -00-00

LEASE NAME Napue

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

990 Ft. from S Section Line

4950 Ft. from E Section Line

LEASE OPERATOR K & E Petroleum, Inc.

SEC. 11 TWP. 7S RGE. 21 ~~KXXXX~~(W)

ADDRESS 300 Hardage Center Wichita, KS 67202

COUNTY Graham

PHONE#(316) 264-4301 OPERATORS LICENSE NO. 5267

Date Well Completed 12-28-87

Character of Well D & A

Plugging Commenced 12-29-87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-29-87

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist #6 Hays, KS Dennis Hamil State Pluggor

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3690

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	235	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

1st plug from 1780 to 1680 with 25sx; pump mud to 970' to 570' with 100sx cement + 2 sx Floclal Pump mud to 270'; 3rd plug from 270' to 110' with 40sx; Pump mud to 40'; 4th plug from 40' to surface with wiper plug for bridge & 10sx cement. Pump 15sx into 1 rathole. All cement 60/40 posmix with 8% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 801 Union Center Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton


(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton
801 Union Center

(Address) Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 31st day of December, 19 87



Janet A. Stuck
Notary Public

Commission Expires: 12-29-90