

15-051-20084-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: ~~15-051-30521-00-00~~
Spot: NENWNE Sec/Twnshp/Rge: 20-13S-19W
4950 feet from S Section Line, 1650 feet from E Section Line
Lease Name: BEMIS Well #: 1-SWD
County: ELLIS Total Vertical Depth: 1247 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

PROD Size: 5.5 feet: 1165 w/400 sxs cmt

Well Type: SWD UIC Docket No: _____ Date/Time to Plug: 06/10/2005 8:30 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: DALE POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: Ordered 150 sxs 60/40 pozmix - 10% gel - 500# hulls.
Records indicate this was an un-permitted SWD.
This is a fee fund plugging.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/10/2005 9:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Allied rigged to 5 1/2" casing with a swedge and pumped 80 sxs 60/40 pozmix with 500# hulls mixed in.
Max. P.S.I. 600#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
962	986		
946	952		
924	936		
906	914		

Remarks: ALLIED CEMENTING COMPANY-TICKET #18708.

Plugged through: CSG

District: 04

Signed _____

(TECHNICIAN)

JUN 13 2005

RECEIVED
JUN 15 2005
KCC WICHITA

