

4-032187

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

12-10

API Number: 15-163-22,582 0000

NW NW SE /4 SEC. 28, 07, 20 W
2310 feet from S section line
2310 feet from E section line

Operator license# 5352

Lease: Cook Well # 4-28 428

Operator: Baird Oil Company, Inc.

County: Rooks

Address: P.O. Box 428
Logan, Kansas 67646

Well total depth 3480 113.10 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 315 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 10 Month: December Year: 1996

Plugging proposal received from: Jim Baird

Company: Baird Oil Company, Inc. Phone:

Were: Order 150 sxs 60/40 pozmix - 10% gel - 500# hulls - 10 sxs gel.

12/17/96

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 9:30 A.M., Day: 10, Month: December, Year: 1996

Actual plugging report: 8 5/8" set at 315' w/215 sxs. cwc. 4 1/2" set at 3459' with 200 sxs. O.H. 3459' - 3480'. Critical area control shots at 1575' and 1000'. Mixed and pumped down 4 1/2" w/25 sxs cement followed by 10 sxs gel, followed by 100 sxs cement blend to Max. P.S.I. 900#. Held. Squeezed backside with 25 sxs cement blend with 100# hulls to Max. P.S.I. 500#. Held. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: GL

I did not observe the plugging.

INVOICED

DATE DEC 31 1996

INV. NO. 47197

1507 Carl Goodrow (agent)