

6 040273

API NUMBER 15-163-22,560 6000 *R*

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SE SW, SEC. 28, T 7 S, R 20 W/E
330 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9747

Lease Name Berland Well # 1-28

Operator: Universal Resources, Inc.
Name & Address: 1125 17th Street
Denver, Colorado 80202

County Rooks 114.56
Well Total Depth 3525 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 263 w/190

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XX

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie License Number 5422
Address Wichita, Ks.

Company to plug at: Hour: PM Day: 21 Month: November Year: 19 84

Plugging proposal received from Bill Craig

(company name) Abercrombie (phone) _____

were: Order 200 sks 50/50 pozmix 6% gel 3% cal. cl. 1 sk hulls and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XX

Operations Completed: Hour: 11:30 PM Day: 21 Month: November Year: 19 84

ACTUAL PLUGGING REPORT

- 1st plug @ 1600 w/40 sks
- 2nd plug @ 900 w/100 sks 2 sks hulls
- 3rd plug @ 275 w/40 sks
- 4th plug @ 40 w/10 sks solid bridge
- 10 sks in Rat Hole.

RECEIVED
STATE CORPORATION COMMISSION
DEC 03 1984
CONSERVATION DIVISION
Wichita, Kansas

12/3/84

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED I (did/did not) observe this plugging.

DATE 12-12-84

Signed Dennis L. Hamel (TECHNICIAN)

INV. NO. 5929

11-30-84 16

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: 11 14 84
month day year 10.15

API Number 15- 163-22,560

OPERATOR: License # 9747
Name Universal Resources, Inc.
Address 1125 17th Street
City/State/Zip Denver, CO 80202
Contact Person Jack L. Partridge
Phone 316-262-1841

SE. SE. SW Sec. 28. Twp. 7. S, Rge. 20 East
(location) West
... 330 ... Ft North from Southeast Corner of Section
... 2970 ... Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5422
Name Abercrombie Drilling, Inc.
City/State Wichita, KS 67202

Nearest lease or unit boundary line 330 feet.
County Rooks
Lease Name Berland Well# 1-28
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Well Drilled For: Well Class: Type Equipment:
 Oil Swd Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Depth to Bottom of fresh water 100 feet
Lowest usable water formation Dakota
Depth to Bottom of usable water 850 feet
Surface pipe by Alternate: 1 2
Surface pipe to be set 250 feet
Conductor pipe if any required None feet
Ground surface elevation 2005 feet MSL
This Authorization Expires 5-13-85
Approved By 11-13-84

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth
Projected Total Depth 3450 feet
Projected Formation at TD Arbuckle
Expected Producing Formations Arbuckle

certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

11-13-84
Signature of Operator or Agent

Jack L. Partridge Title V.P. Abercrombie Drilling
Jack L. Partridge
MHC-KONE 11/13/84
Form C-1 4/84

RECEIVED
STATE CORPORATION COMMISSION
DEC 03 1984
CONSERVATION DIVISION
Wichita, Kansas