

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22870-00-00
Spot: NWSW Sec/Twnshp/Rge: 16-7S-21W
1750 feet from S Section Line, 4640 feet from E Section Line
Lease/Unit Name: INSLEY Well Number: 1
County: GRAHAM Total Vertical Depth: 3711 feet

Operator License No.: 9449
Op Name: GREAT EASTERN ENERGY & DEV. CO
Address: 550 W. TEXAS STE 660
MIDLAND, TX 79702

Surface Casing Size: 8.625 feet: 234 \$120.61

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/14/2003 7:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: BILL WYNN Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 02/14/2003 12:00 PM KCC Agent: HERB DEINES

Actual Plugging Report:


1st. Plug 1750' w/25 sxs. Anhydrite 1714' - 1746'.
2nd. Plug 1000' w/100 sxs. Dakota 659' - 959'.
3rd. Plug 285' w/40 sxs. Surface pipe 234'.
4th. Plug 40' w/10 sxs.
Rathole with 15 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed _____



(TECHNICIAN)

RECEIVED
FEB 20, 2003
FEB 20 2003

INVOICED

Form CP-2/3

DATE 2-24-03

INV. NO. 2003061218

FEB 19 2003

KCC WICHITA