

6 070675

4-19-88

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065-22,450-00-00
150' S E/2 E/2 NW, SEC. 14, T 7 S, R 21 W/

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Operator: Ritchie Exploration Inc.
Name & Address: 125 N. Market #1000
Wichita, Ks. 67202
Jeff Christian

3810 feet from S section line
2970 feet from E section line

Lease Name Kenyon Well # 1
County Graham 116.19
Well Total Depth 3575 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 215

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ U&A

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Co. License Number 6033

Address 250 North Water #300 Wichita, Ks. 67202

Company to plug at: Hour: 7:30AM Day: 19 Month: April Year: 19 88

Plugging proposal received from Lloyd Dellette

(company name) Murfin Drilling Company (phone) _____

were: 8 5/8" - 215' S.P. cwc w/170 sks 60/40 Poz 2% Gel 3% Ca Cl (By Allied)

Did not penetrate arbuttle, Ely. 2091' Anhy 1715'. No circulation problems.

Proposal 215 sks 60/40 Poz 6% Gel 3% Ca Cl 1 sk Celloflake and 8 5/8" plug.

Spot with drill stem, recondition hole, heavy mud between all plugs.

25 sks at 1725'; 100 sks w/915'; 40 sks at 260'; 10 sks at 40'; 15 sks rat hole.

(Circulate) Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 7:30AM Day: 19 Month: April Year: 19 88

ACTUAL PLUGGING REPORT Ordered 215 sks 60-40 Poz 6% Gel 3% Ca Cl 1sk

Celloflake and 8 5/8" plug. Spotted with drill stem, circulated. Heavy mud between all plugs. 1st plug at 1725' w/25 sks cement. 2nd plug at 915' w/100 sks cement and w/1 sk Celloflake; 3rd plug at 260' w/40 sks cement. 4th plug Hulls plug at 40' w/10 sks cement. 15 sks in rat hole (circulate)

Remarks: Cemented by Allied Cement. (If additional description is necessary, use BACK of this form.)

I (operator) do not conserve this plugging.

DATE 7-8-88

INV. NO. 21243

JUL 6 1988

Signed Marion J. Schmidt (TECHNICIAN)