

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5131

Operator: Thunderbird Drilling Co. Inc.
Name &
Address P.O. Box 18407, Wichita, KS 67212

API NUMBER 15-163-21, 8290000

NW, Sec. 27, T 7 S, R 20 W/E

990 feet from (N)S section line

330 feet from (W)E section line

Lease Name Hamel Well # 1

County Rock

Well Total Depth 3520' feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 371'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Thunderbird Drilling Co. Inc. License Number 38

Address P.O. Box 18407, Wichita, KS 67212

Company to plug at: Hour: 5:45 AM Day: 27 Month: 10 Year: 19 82

VERBAL PLUGGING ORDERS GIVEN TO Ed Cook

(company name) Thunderbird Drilling Co. Inc. (phone) 316-685-1441

were: Order 180 sacks 50 permix - 4% gel - 3% gel. U. + 8 5/8" plug. spot w/
drill stem w/ heavy mud between all plugs. 1st plug C 3520' w/ 20 sacks
2nd plug C 1540' w/ 20 sacks, 3rd plug C 800' w/ 80 sacks, 4th plug C 400'
w/ 40 sacks, 5th plug - solid bridge of balls C 40' w/ 10 sacks.
Circulate 10 sacks in rat hole.

Signed Ruth E. L. Luf
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:45 AM Day: 27 Month: 10 Year: 19 82

ACTUAL PLUGGING REPORT 8 5/8" - 371' w/ 225 sacks common - 2% gel - 3% gel. U.

Ordered 180 sacks 50 permix - 4% gel - 3% gel. U. + 8 5/8" plug. spot w/ drill
stem w/ heavy mud between all plugs. 1st plug C 3520' w/ 20 sacks,
2nd plug C 1540' w/ 20 sacks, 3rd plug C 800' w/ 80 sacks, 4th plug C
400' w/ 40 sacks, 5th plug - solid bridge of balls + plug C 40' w/ 10 sacks.
Circulated 10 sacks in rat hole.

Remarks: _____

RECEIVED
STATE CORPORATION COMMISSION

NOV 08 1982

CONSERVATION DIVISION
Wichita, Kansas

11/8/82

I hereby certify that the above plugging instructions were given as herein stated
and that I ~~did~~ / did not) observe this plugging.

INVOICED

DATE 12-6-82
INV NO. 1776-44

Signed Ruth E. L. Luf
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82