

6010222

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163=22,4736000

NW, SEC. 26, T. 7 S, R. 20 (W/E)
3420 feet from N/S section line
4970 feet from W/SE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140

Lease Name Hansen Well # 1

Operator: Frontier Oil Company

County Rooks

Name & Address 1720 K.S. Band Bldg.

Well Total Depth 3500 113.75 feet

Wichita, Ks.

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 362.95

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XX

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Company License Number 5302

Address Same as above

Company to plug at: Hour: AM Day: 20 Month: September Year: 19 84

Plugging proposal received from Kenney Bieker

(company name) Red Tiger (phone) _____

were: Order 210 sks cmt 50/50 pozmix 6% gel 3% cal. cl., 1 sk hulls 8 5/8" plug 1 sk flo-seal

Spot drill pipe with no less than 36 vis mud between all plugs, with good circulation and no fluid loss.

Plugging Proposal Received by Dale F. Balthazor (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XX

Operations Completed: Hour: 11 AM Day: 20 Month: September Year: 19 84

ACTUAL PLUGGING REPORT Circulated at 3490 for 30 minutes.

1st plug @ 3490 w/25 sks

2nd plug @ 1530 w/25 sks

3rd plug @ 870 w/100 sks mixed with 1 sk flo seal

4th plug @ 380 w/40 sks

5th plug @ 40 w/10 sks on solid bridge 10 sks in Rat Hole

Remarks: Cemented by Allied

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-2-84

INV. NO. 3971

Signed Dale F. Balthazor (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION 9/24/84 SEP 24 1984

CONSERVATION DIVISION WICHITA, KANSAS

9-21-84 MSB 29